

PLAN	SURVEYED	DATE
	PLANNED	
	NOTED	
	CHECKED	
	BY	
	NOTE BOOK	
	NO.	
	CADD FILE NAME	

PROFILE	SURVEYED	DATE
	PLANNED	
	NOTED	
	CHECKED	
	BY	
	NOTE BOOK	
	NO.	
	STRUCTURE NOTATIONS CHKD	

	UNDERCUT AND PGE REPLACEMENT (CY)*	UNSUITABLE EXCAVATION (TOPSOIL) (CY)	EARTH EXCAVATION (CY)	EXCAVATION TO BE USED FOR EMBANKMENT (CY)	EMBANKMENT REQUIRED (CY)	EARTHWORK BALANCE WASTE (+) / SHORTAGE (-)
RIFORD ROAD						
100+00 TO 105+00	0	67	651	553	33	520
105+00 TO 110+00	0	21	458	390	144	245
110+00 TO 115+00	120	99	956	812	63	749
115+00 TO 120+00	48	103	728	619	94	524
120+00 TO 125+00	48	70	768	652	82	570
125+00 TO 129+18	0	14	1073	912	109	802
ST CHARLES ROAD						
45+00 TO 49+00	0	72	151	128	40	88
49+00 TO 55+00	0	91	404	343	30	314
TOTALS	216	536	5187	5033	728	3813

SHRINKAGE FACTOR = 0.85

EARTHWORK TABLE