STATION 240+00

STATION 245+00

MATCHLINE

MATCHLINE

(CONNECT TO EX. STRUCTURE)

(SS-1-12" RCCP, CI IV, 5 FT @ 1.0%)

MAILBOX REMOVAL/RELOCATION (2)

60SF BLOCK WALL REMOVAL

70SF SEGMENTAL CONCRETE BLOCK WALL

REMOVE PLANTER AND MATERIALS IN R.O.W. AS REQUIRED

HEDGE REMOVAL, 40FT

STATION 240+16, 16'RT
INLET TYA-2'-TY8 GRATE
RIM=779.00
INV 12"=776.00

EX. STORM MH
RIM=779.70
INV 15" S=771.21
INV 15" N=769.00

(CORE DRILL HOLE IN MH AND CONNECT NEW 12" @ INV=768.98 COST INCLUDED IN PRICE OF INLET)

*TYPE 8 GRATE REMOVAL
*TYPE 1 FRAME, CL (2)

REMOVE TREE, 30"DIA.

LOTUS DRIVE

N

SCALE:
HOR: 1"=20'
VER: 1"=2'

NOTE:
EXISTING PIPE CULVERT CONNECTIONS TO MANHOLES INCLUDED IN COST OF PIPE CULVERT (TYP.)

NOTE:
LANDSCAPE/DECORTIVE PLANTINGS WITHIN CONSTRUCTION LIMITS IN R.O.W. ARE TO BE REMOVED/DISPOSED OF OFF-SITE, COST TO BE INCLUDED IN EARTH EXCAVATION.

EX. ℄ PAVEMENT

PROPOSED B/SIDEWALK (EAST)

FILE NAME = 10258806.DWG	USER NAME =	DESIGNED — RJD	REVISED —
	FILE NAME =	DRAWN — EC	REVISED —
	PLOT SCALE =	CHECKED — RJD	REVISED —
	PLOT DATE =	DATE — 10/02/09	REVISED —

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE

SCALE: 1"=20' | SHEET NO. 32 OF 73 SHEETS | STA. 240+00 TO STA. 245+00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	08-00062-00-SW	LAKE	73	32
		CONTRACT NO. 63280		
		ILLINOIS FED. AID PROJECT		