



HMA SURFACE REMOVAL & RESURFACING
STA. 1+48.41 TO STA. 5+50 (1395 SQ YDS)

- | | |
|---|---|
| ① PR CB TYPE A, 4' DIA., EX T1 FR, CL
STA. 1+73.85, 15.86' LT
RIM = 38.32
INVERT = 33.95 | ① 16 LF 8" PVC SDR 26 SS, CL B TY 2 @ 17.7% |
| ② PR INL TYPE A, EX T1 FR, CL
STA. 3+78.06, 16.35' LT
RIM = 38.12
INVERT = 35.12 | ② 5 LF 8" PVC SDR 26 SS, CL B TY 2 @ 5.0% |
| ③ PR CB TYPE A, 4' DIA., EX T1 FR, CL
STA. 3+81.12, 13.97' LT
RIM = 38.39
INVERT = 34.40 | ③ 13 LF 8" PVC SDR 26 SS, CL B TY 2 @ 4.1% |
| ④ PR CB TYPE A, 4' DIA., EX T1 FR, CL
STA. 3+79.80, 16.01' RT
RIM = 38.15
INVERT = 34.15 | ④ 15 LF 8" PVC SDR 26 SS, CL B TY 2 @ 2.6% |
| ⑤ PR INL TYPE A, EX T1 FR, CL
STA. 5+19.64, 16.44' LT
RIM = 38.09
INVERT = 35.20 | ⑤ 5 LF 8" PVC SDR 26 SS, CL B TY 2 @ 4.0% |

- | | |
|--|---|
| ⑥ PR CB TYPE A, 4' DIA., T1 FR, CL
STA. 5+22.04, 13.29' LT
RIM = 38.40
INVERT = 34.30 | ⑥ 12 LF 8" PVC SDR 26 SS, CL B TY 2 @ 16.4% |
| ⑦ PR CB TYPE A, 4' DIA., T1 FR, CL
STA. 5+34.91, 16.14' RT
RIM = 38.09
INVERT = 34.09 | ⑦ 15 LF 8" PVC SDR 26 SS, CL B TY 2 @ 12.6% |

LEGEND

- PROPOSED BUTT JOINT
- REMOVE & REPLACE CURB & GUTTER
- REMOVE & REPLACE SIDEWALK
- DETECTABLE WARNINGS
- EX MANHOLE
- EX CATCH BASIN
- PR CATCH BASIN
- EX INLET
- PR INLET
- EX COMBINED SEWER
- PROPOSED STORM SEWER
- EX WATER
- EX GAS
- EX ELECTRIC

FILE NAME = 01-shtr-plan1.dgn	USER NAME = default	DESIGNED - RB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EAST AVENUE STATION 1+48.41 TO STATION 5+50	F.A.U. RTE. 2779	SECTION 09-00246-00-RS	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 7
PLOT SCALE = #SCALE#				SCALE: 1" = 20'		SHEET NO. 7 OF 25 SHEETS		STA. 1+48.41 TO STA. 5+50		ILLINOIS FED. AID PROJECT
PLOT DATE = 2/16/2010				DATE - SEPTEMBER 2009		CONTRACT NO. 63293				