



- 11 PR INLET TYPE A, (EXISTING FR & LID)
 STA. 12+07.66, 16.40' LT
 RIM = 37.55
 INVERT = 34.55
- 11 5 LF 8" PVC SDR 26 SS, CL B TY 2 @ 7.6%
- 12 PR CB TYPE A, 4' DIA., (EXISTING FR & LID)
 STA. 12+08.57, 15.53' RT
 RIM = 37.55
 INVERT = 33.55
- 12 15 LF 8" PVC SDR 26 SS, CL B TY 2 @ 15.6%
- 13 PR CB TYPE A, 4' DIA., (EXISTING FR & LID)
 STA. 13+72.69, 15.86' RT
 RIM = 37.60
 INVERT = 33.10
- 13 15 LF 8" PVC SDR 26 SS, CL B TY 2 @ 16.5%
- 14 PR CB TYPE A, 4' DIA., (EXISTING FR & LID)
 STA. 15+96.27, 15.80' LT
 RIM = 38.00
 INVERT = 33.50
- 14 14 LF 8" PVC SDR 26 SS, CL B TY 2 @ 8.9%
- 15 PR CB TYPE A, 4' DIA., (EXISTING FR & LID)
 STA. 15+96.72, 15.32' RT
 RIM = 38.00
 INVERT = 33.50
- 15 14 LF 8" PVC SDR 26 SS, CL B TY 2 @ 8.9%

HMA SURFACE REMOVAL & RESURFACING
 STA. 11+00 TO STA. 16+50 (2095 SQ YDS)

LEGEND	
	PROPOSED BUTT JOINT
	REMOVE & REPLACE CURB & GUTTER
	REMOVE & REPLACE SIDEWALK
	DETECTABLE WARNINGS
	EX MANHOLE
	EX CATCH BASIN
	PR CATCH BASIN
	EX INLET
	PR INLET
	EX COMBINED SEWER
	PROPOSED STORM SEWER
	EX WATER
	EX GAS
	EX ELECTRIC

FILE NAME = DI-shtr-plan3.dgn	USER NAME = default	DESIGNED - RB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EAST AVENUE STATION 11+00 TO STATION 16+50			F.A.U. RTE. 2779	SECTION 09-00246-00-RS	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 9
	PLOT SCALE = #SCALE#	DRAWN - LB	REVISED -		SCALE: 1" = 20'	SHEET NO. 9 OF SHEETS	STA. 11+00 TO STA. 16+50	CONTRACT NO. 63293				
	PLOT DATE = 2/16/2010	CHECKED - LB	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - SEPTEMBER 2009	REVISED -									