

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, SUMMARY OF QUANTITIES
3	GENERAL NOTES
4-5	SCHEDULE OF QUANTITIES
6-7	TYPICAL SECTIONS
8-13	PLAN SHEETS
14-19	PAVEMENT MARKING SHEETS
20-27	TRAFFIC SIGNAL AND CABLE PLANS
28-29	VILLAGE OF LOMBARD STANDARD DETAILS
30	TS-07 DETECTOR LOOP INSTALLATION DETAIL FOR ROADWAY RESURFACING
31	TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
32	TC-22 TEMPORARY INFORMATION SIGNING
33	BD-8 DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
34	BD-32 BUTT JOINT AND HMA TAPER DETAILS
35	TC-13 DISTRICT 1 TYPICAL PAVEMENT MARKINGS
36	TC-16 PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING

HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
424001-05	CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C AND D PATCHES
602301-02	INLET - TYPE A
602401-02	MANHOLE, TYPE A
602701-02	MANHOLE STEPS
604001-03	FRAMES AND LIDS, TYPE 1
604006-04	FRAME AND GRATE, TYPE 3
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701501-05	URBAN LANE CLOSURE, 2L, 2W UNDIVIDED
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
886001-01	DETECTOR LOOP INSTALLATIONS
886006-01	TYPICAL LAYOUTS FOR DETECTION LOOPS

VILLAGE OF LOMBARD STANDARD DRAWINGS

DRAWING NO.	TITLE
PAVEMENT 2	SIDEWALK CROSS SECTION
PAVEMENT 4	SIDEWALK CONSTRUCTION
PAVEMENT 5	TYPICAL PAVEMENT CROSS-SECTION
PAVEMENT 6	RESIDENTIAL DRIVEWAY APRON
PAVEMENT 7	COMMERCIAL DRIVEWAY APRON
PAVEMENT 8	CURB AND GUTTER
PAVEMENT 9	STORM SEWER INLET CURB AND GUTTER
STORM 2	INLET TYPE A
STORM 7	RIM ADJUSTMENTS PAVED AREA
STORM 8	RIM ADJUSTMENTS IN CURB LINE
STORM 12	GRATE BOX INLET
SANITARY 1	SANITARY MANHOLE

SUMMARY OF QUANTITIES

PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY 1000
20101100	TREE TRUNK PROTECTION	EACH	75
** 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	18
** 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	45
25200200	SUPPLEMENTAL WATERING	UNIT	2
** 25200700	SODDING, SPECIAL	SQ YD	45
28000510	INLET FILTERS	EACH	55
** 31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	18
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,168
40600300	AGGREGATE (PRIME COAT)	TON	64
** 40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	5
** 40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75 N50	TON	1,049
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	209
40603340	HMA SURFACE COURSE, MIX "D", N70	TON	3,154
42001300	PROTECTIVE COAT	SQ YD	1,699
** 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	8,259
** 42400800	DETECTABLE WARNINGS	SQ FT	422
44000155	HMA SURFACE REMOVAL, 1 1/2"	SQ YD	11,706
44000162	HMA SURFACE REMOVAL, 3 1/4"	SQ YD	19,977
44000600	SIDEWALK REMOVAL	SQ FT	8,259
** 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,507
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	208
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	795
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	2,106
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	7,000
** 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	9
60250200	CATCH BASINS TO BE ADJUSTED	EACH	6
** 60250300	CATCH BASINS TO BE ADJUSTED (SPECIAL)	EACH	4
60255500	MANHOLES TO BE ADJUSTED	EACH	9
** 60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	7
60260100	INLETS TO BE ADJUSTED	EACH	12
** 60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	25
60262700	INLETS TO BE RECONSTRUCTED	EACH	2
** 60265800	VALVE VAULTS TO BE ADJUSTED (SPECIAL)	EACH	23
** 60266610	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	5
** 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	42
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	50
60500040	REMOVING MANHOLES	EACH	1
67100100	MOBILIZATION	L SUM	1
** 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
** 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
** 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* ** 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	250
* ** 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	14,043
* ** 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3,013
* ** 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	643
* ** 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	454
* ** 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4
* ** 88600600	DETECTOR LOOP REPLACEMENT	FOOT	75
* 89502200	MODIFY EXISTING CONTROLLER	EACH	4
** 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,599
** X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	15
** X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51
** XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	160
** XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1
* ** XX005723	VIDEO DETECTION SYSTEM, COMPLETE INTERSECTION	EACH	4
** XX005972	STAMPED ASPHALT CROSSWALK	SQ YD	234
* ** XX007246	ELECTRIC CABLE IN CONDUIT NO. 18 3C	FOOT	2,327
** XX007509	REMOVE AND REPLACE SANITARY MANHOLES, 4' DIAMETER, 0-8 FEET DEEP	EACH	10
** XX007510	REMOVE AND REPLACE SANITARY MANHOLES, 4' DIAMETER, 8-12 FEET DEEP	EACH	9
** XX008264	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT (SPECIAL)	FOOT	1,285

* DENOTE SPECIALTY ITEM

** INDICATES ITEM COVERED BY SPECIAL PROVISIONS

I:\LMBD\090317-01 Char_LAPP\CADD-SURVEY\DRAWINGS\DWGS\090317-BEN-NOTES.dwg - 01
 Plotted: 2-08-10 @ 4:19pm By: 560kar
 Copyright © 2009, By Baxter & Woodman, Inc.
 State of Illinois - Professional Design Firm
 License No. - 184-001121 - Expires 4-30-11



DESIGNED - TMS	REVISED - PER VILLAGE REVIEW 09-09-09
DRAWN - KAR	REVISED - PER VILLAGE REVIEW 09-16-09
CHECKED -	REVISED - PER IDOT REVIEW 09-17-09
DATE - 06-26-09	REVISED - PER IDOT FINAL COMMENTS 01-18-10

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

INDEX OF SHEETS, HIGHWAY STANDARDS, SUMMARY OF QUANTITIES

SCALE: PROJECT NO: 090317 STA. TO STA.

F.A.P. RITE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1397	09-00153-00-RS	DuPAGE	36	2
CONTRACT NO. 63351				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-ARA-9003(421)				