SCHEDULE OF QUANTITIES - STRUCTURES

STRUCTURE INFO					EXISTING PAY ITEM								PROPOSED PAY ITEM																			
				PAY ITEM CODE	56200300	* 60249300	* 60249400	60500040	60500050	60500060	* X0323517	* XX007535	* 56104800	* 56104900	* 56105000	* 56105200	56200700	* 60202905	* 60203240	60218400	60218400	60221100	* 60233500	* X0323168	60237460	* 56400500	* 56400820	* 60248700	* 60248900	20200200	* X0323868	* Z0050500
SHEET	STRUCTURE #	STATION	OFFSET	BASE LINE	FH REMOVE	VV REMOVE	VB REMOVE	MH REMOVE	CB REMOVE	INL REMOVE	VV ABANDON, REM CN F&L	GULFBOX TO BE ADJUSTED	4" VALVE	6" VALVE	8" VALVE	12" VALVE	FH AUX VALVE & BOX	CB TA SPEC 4D T1F CL	CB TA SPEC 4D T23F&G	MH TY A TY 1 F&CL (SAN)	MH TY A 4' DIA TY 1 F&CL	MH TY A 5' DIA TY 1 F&CL	PR T MH 60D SS T1FCL	DROP CONNECTION	INL TY A TY 23 F&G	VV TY A, 4' DIA. TY 1 F&CL	VV TY A, 5' DIA. TY 1 F&CL	VALVE BOXES 4"	VALVE BOXES 6"	ROCK EXCAVATION	DRAINAGE RESTRICTOR	STREET LIGHT RELOCATE
47	68	0+67.61	9.94'L	4												1											1					
47	87	0+87.18	19.37'L	4							1																					
47	147	1+46.75	8.68'R	4											1											1						
47	149	1+48.55	34.21'L	4			1							1												1						
47	151	1+50.84	8.67'L	4		1																										
40	155	1+54.91	14.36'R	4					1																							
40	159	1+58.16	15.12'L	4					1																							
47	162	1+61.59	22.93'L	4	1																											
47	168	1+67.84	17.92'L	4			1																									
54	178	1+78.00	24.00'R	4																												1
40	183	1+83.77	18.00'L	4																					1							
40	184	1+83.77	18.00'R	4															1													
47	201	2+00.77	23.10'L	4													1															
47	205	2+05.77	7.00'L	4												1											1					
40	311	3+12.46	17.65'R	4															1													
40	312	3+12.46	7.00'R	4																	1											
40	313	3+12.46	17.79'L	4															1													
54	325	3+25.00	24.50'L	4																												1
40	350	3+50.00	23.35'R	4																1												
40	355	3+54.50	15.39'R	4					1																							
40	356	3+55.95	13.89'L	4						1																						
40	362	3+61.33	20.10'R	4				1																								
54	445	4+45.00	24.23'R	4																												1
54	447	4+47.17	18.83'L	4								1																				
47	490	4+90.00	19.74'L	4													1															
41	553	5+53.35	12.02'L	4						1																						
41	554	5+53.55	17.29'R	4					1																							
41	558	5+58.31	21.28'R	4				1																								
55	598	5+99.00	20.30'L	4																												1
41	599	6+00.00	12.23'R	4															1													
41	600	6+00.00	7.00'R	4																	1											
41	601	6+00.00	12.24'L	4															1													
41	610	6+10.00	19.10'R	4																1												
41	671	6+70.44	22.42'R	4				1																								
48	676	6+75.63	24.60'R	4										1															1			
48	678	6+78.45	10.12'L	4			1																									
48	684	6+84.45	10.07'L	4							1																					
48	688	6+87.57	20.71'L	4									1															1				
55	732	7+31.66	18.29'L	4								1																				
48	735	7+35.00	7.00'L	4												1											1					
48	785	7+85.00	18.81'L	4													1															
48	811	8+11.50	10.68'L	4							1																					
41	816	8+16.41	18.21'R	4					1																							
41	817	8+16.96	11.20'L	4						1																						
41	824	8+25.00	12.00'L	4															1													
41	825	8+25.00	7.00'R	4																	1											
41	826	8+25.00	12.00'R	4															1													
48	827	8+25.34	9.23'L	4							1																					
48	828	8+26.57	21.25'L	4	1																											
48	829	8+25.21	23.26'L	4												1											1					
41	840	8+40.00	19.10'R	4																1												
41	841	8+39.99	12.42'L	4					1																							
41	850	8+49.92	19.04'R	4				1																								
41	936	9+35.17	20.00'R	4															1													
55	1009	10+08.93	20.49'L	4								1																				
41	1030	10+30.40	13.50'R	4																1												
55	1099	10+09.57	25.75'R	4																												1
48	1031	10+31.17	11.80'L	4							1																					
48	1032	10+32.09	23.01'L	4										1															1			
48	1063	10+63.86	25.28'R	4			1																									
48	1068	10+67.77	25.09'R	4										1															1			
41	1071	10+70.67	17.28'R	4					1																							
41	1072	10+71.68	11.11'L	4						1																						
41	1076	10+75.83	15.58'R	4				1																								
48	1079	10+79.11	17.10'L	4													1															
42	1109	11+10.00	25.00'L	4														1														
42	1110	11+10.00	7.00'R	4																	1											
49	1165	11+65.00	7.00'L	4												1											1					
56	1175	11+75.70	21.58'L	4								1																				
42	1179	11+79.82	12.00'L	4															1													
42	1207	12+07.55	12.99'R	4				1																								
49	1221	12+21.17	33.94'L	4			1								1											1						
56	1234	12+34.35	21.88'L	4								1																				
42	1249	12+50.00	12.00'L	4															1													
42	1250	12+50.00	7.00'R	4																	1											
42	1251	12+50.00	20.00'R	4															1													
42	1252	12+50.03	16.93'R	4					1																							
42	1253	12+51.34	11.29'L	4					1																							
42	1259	12+59.26	12.97'R	4				1																								
56	1325	13+25.00	25.55'R	4																												1
56	1336	13+36.29	20.80'L	4								1																				
42	1340	13+40.00	13.50'R	4																1												
42	1469	14+70.34	12.00'L	4															1													
42	1470	14+70.34	7.00'R	4																		1										

* = DENOTES SPECIALTY ITEM

HEUER AND ASSOCIATES
Consulting Engineers
2315 Enterprise Drive - Suite 102 Westchester, IL 60154-5811 708-492-1000

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
1004	08-00079-03-FP	COOK	94	5
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT No. 63353

REVISIONS	
NAME	DATE
PER IDOT	01-14-10

ILLINOIS DEPARTMENT OF TRANSPORTATION

BLUFF AVENUE IMPROVEMENTS STAGE 3

SCHEDULE OF QUANTITIES

SCALE:
DATE 11/30/2009

DRAWN BY H&A
CHECKED BY JRH

PLAN
NOTE BOOK NO.
SURVEYED
PLOTTED
ALIGNMENT CHECKED
BK. PAGE NO. REVISED
CADD FILE NAME
3"
DATE

PROFILE
NOTE BOOK NO.
SURVEYED
PLOTTED
GRADES CHECKED
BK. PAGE NO. REVISED
STRUCTURE NOTATIONS CHKD
BY
DATE