

SCHEDULE OF QUANTITIES - SEWER PIPE

		PAY ITEM CODE		PROPOSED PAY ITEM																		
		550A0800	550B0320	550B0320	550B0330	550B0330	550B0340	550B0340	550B0360	550B0380	550B0380	550B0410	20200200	20800150								
		UNDERGROUND INFO																				
SHEET	UPSTREAM STRUCTURE # or (STATION)	UPSTREAM DEPTH	DOWNSIDE STRUCTURE # or (STATION)	DOWNSIDE DEPTH	AVERAGE DEPTH	60" RCP IN TRENCH RELIEF	8" PVC STORM	8" PVC COMBINATION	10" PVC SANITARY	10" PVC STORM	12" PVC COMBINATION	12" PVC STORM	15" PVC STORM	18" RCP COMBINATION	18" RCP STORM	24" RCP STORM	ROCK EXCAVATION	TRENCH BACKFILL CA-6, CY				
40	183	4.00	184	4.22	4.1		37											2.7				
40	184	4.49	312	5.08	4.8													15.2				
40	(310)	4.50	311	4.00	4.3		15						129					1.3				
40	311	4.00	312	4.54	4.3					11								0.9				
40	313	3.99	312	4.83	4.4					25								2.3				
40	312	5.28	600	5.70	5.5								288					50.4				
40	350	3.61	610	3.49	3.6													0.0				
41	599	4.00	600	4.31	4.2		5			260								0.4				
41	601	4.17	600	4.76	4.5									19				1.7				
41	600	5.90	825	7.57	6.7										225			84.1				
41	610	3.59	840	5.08	4.3					230								0.0				
41	(724)	7.50	(728)	7.50	7.5		34											12.0				
41	(757)	3.95	(758)	6.40	5.2		19											3.1				
41	824	4.17	825	4.76	4.5							19						1.7				
41	826	4.00	825	4.31	4.2		5											0.4				
41	825	7.97	1110	10.20	9.1											285	41.9	201.4				
41	840	5.18	1030	5.60	5.4				190									17.8				
41	936	3.58	(935)	9.00	6.3					12								3.1				
42	1030	5.70	1340	7.12	6.4				310								1.5	82.7				
42	1109	10.54	1110	9.60	10.1							32						21.0				
42	1110	10.20	1250	10.56	10.4											140		125.9				
42	1179	4.00	(1180)	10.70	7.4					19								6.8				
42	1249	4.04	1250	4.62	4.3					19								1.5				
42	1251	4.00	1250	4.62	4.3					13								1.0				
42	1250	10.56	1470	11.68	11.1											220		220.7				
42	1340	7.22	1480	7.44	7.3				140									48.5				
42	1469	4.04	1470	4.63	4.3					19								1.5				
42	1471	4.00	1470	4.63	4.3					13								1.0				
42	1470	11.68	1550	12.34	12.0											80		90.9				
42	1480	7.54	1573	8.21	7.9													38.0				
42	1550	13.79	(1574)	14.00	13.9				95							34	6.3	48.2				
42	1655	7.55	1573	8.21	7.9				85								16.8	34.0				
42	1665	13.37	(1588)	14.00	13.7											80		111.1				
43	2005	7.72	1655	7.45	7.6				350									130.7				
43	1664	4.04	1665	4.63	4.3		19											1.7				
43	1666	4.00	1665	4.63	4.3					13								1.0				
43	1845	12.55	1665	12.37	12.5											179	17.4	216.7				
43	1844	4.00	1845	4.59	4.3		19											1.7				
43	1846	9.38	1845	9.83	9.6									13				9.6				
43	(1847)	9.50	1846	9.38	9.4									21				15.0				
43	2229	8.98	1845	10.80	9.9									384				299.1				
43	2271	5.73	2005	7.62	6.7				266									78.0				
44	2228	4.36	2229	5.03	4.7		13											1.6				
44	2259	4.00	2229	5.03	4.5		35											3.7				
44	2600	6.02	2229	8.98	7.5											370		175.7				
44	2480	4.17	2271	5.63	4.9													27.7				
44	2599	4.04	2600	4.63	4.3				19									1.5				
44	2601	4.63	2600	5.26	4.9					13								1.7				
44	2750	5.44	2600	5.82	5.6							150						27.8				
44	2749	4.04	2750	4.63	4.3		19											1.7				
44	2751	4.00	2750	4.63	4.3		13											1.2				
44	2893	4.67	2750	5.11	4.9					143								19.1				
45	2905	4.14	2893	4.53	4.3		23											2.0				
45	2906	4.00	2893	4.53	4.3		18											0.0				
46	(6050)	6.50	6055	6.27	6.4									5				1.7				
46	6055	8.13	1573	8.82	8.5													0.0				
46	1573	8.31	6152	8.82	8.6				46			52						24.8				
46	(6041)	16.00	(6046)	16.00	16.0		5										5.9	13.6				
46	(6046)	16.00	(6075)	16.00	16.0		31											27.6				
46	(6075)	16.00	(1588)	16.00	16.0		14											12.4				
46	(1588)	16.00	(1574)	16.00	16.0		24											21.3				
46	(1574)	16.00	(6147)	16.00	16.0		34											25.9				
TOTALS						108	274	46	2,134	319	52	167	470	5	1,013	1,018	177	2,569				

SCHEDULE OF QUANTITIES - WATER MAIN

		PAY ITEM CODE		UNDERGROUND INFO														
		56103000	56103100	56103300	60266910	20800150												
SHEET	STRUCTURE # or (STATION)	DEPTH	STRUCTURE # or (STATION)	DEPTH	AVERAGE DEPTH	6" DIP	8" DIP	12" DIP	WATER MAIN CASING 24"	TRENCH BACKFILL								
47	68	5.50	(79)	5.50	5.5				40									9.9
47	(78)	7.50	(98)	7.50	7.5								20					0.0
47	(79)	6.00	(159)	6.00	6.0				80									23.6
47	147	5.50	(148)	5.50	5.5				41									9.9
47	(148)	5.50	149	5.50	5.5	5												1.2
47	(148)	5.50	(196)	5.50	5.5		57											13.8
47	(159)	5.50	(196)	5.50	5.5				30									7.4
47	(196)	5.50	(201)	5.50	5.5				5									1.2
47	(201)	5.50	205	5.50	5.5				5									1.2
47	(201)	5.50	201	5.50	5.5	16												3.8
47	205	5.50	(490)	5.50	5.5				284									70.3
47	(490)	5.50	490	5.50	5.5	13												3.1
48	(490)	5.50	(673)	5.50	5.5				183									45.3
48	(673)	5.50	(690)	5.50	5.5				17									4.2
48	(690)	5.50	688	5.50	5.5													0.0
48	(690)	5.50	735	5.50	5.5				45									11.1
48	735	5.50	(785)	5.50	5.5				50									12.4
48	(785)	5.50	785	5.50	5.5	12												2.9
48	(785)	5.50	(835)	5.50	5.5				50									6.5
48	(835)	5.50	829	5.50	5.5				28									6.9
48	(835)	5.50	(1037)	5.50	5.5				202									50.0
48	(1037)	5.50	(1074)	5.50	5.5				37									9.2
48	(1074)	5.50	(1079)	5.50	5.5				5									1.2
48	(1079)	5.50	1079	5.50	5.5	10												2.4
49	(1079)	5.50	1165	5.50	5.5				86									21.3
49	1165	5.50	(1219)	5.50	5.5				54									13.4
49	(1219)	5.50	1221	5.50	5.5		27											6.5
49	(1219)	5.50	1524	5.50	5.5				304									75.2
49	1524	5.50	(1545)	5.50	5.5				21									5.2
49	(1545)	5.50	(1584)	5.50	5.5				39									9.7
49	(1584)	5.50	1656	5.50	5.5				72									17.8
50	1656	5.50	(1860)	5.50														