

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	J000-2A	SFTY-1B	SFTY-1B	Y031-1F	Y031-1F	Y060
				ROADWAY	SIDEWALK (STA. 113+74 TO STA. 118+85, RT)	SIDEWALK (STA. 98+39 TO STA. 107+87)	TRAFFIC SIGNALS	EMERGENCY VEHICLE PRE-EMPTION	WATERMAIN
				70% FEDERAL / 30% VILLAGE	80% FEDERAL / 20% VILLAGE	80% FEDERAL / 20% VILLAGE	70% FEDERAL / 30% VILLAGE	100% VILLAGE	100% VILLAGE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	329	134	14	181			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	196	20	176				
20101000	TEMPORARY FENCE	FOOT	3040	3040					
20101100	TREE TRUNK PROTECTION	EACH	82	82					
20101200	TREE ROOT PRUNING	EACH	82	82					
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	65	65					
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	17	17					
20200100	EARTH EXCAVATION	CU YD	4405	4405					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1231	1231					
20400800	FURNISHED EXCAVATION	CU YD	1375	827	190	358			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1231	1231					
20800150	TRENCH BACKFILL	CU YD	3586	2460	5	13			1108
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8905	5847	910	2148			
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	350	350					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	110	72	11	27			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	110	72	11	27			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	110	72	11	27			
25200110	SODDING, SALT TOLERANT	SQ YD	8905	5847	910	2148			
25200200	SUPPLEMENTAL WATERING	UNIT	134	134					
25300600	TRANSPLANTED SALVAGED TREES	EACH	10	10					
25300700	TRANSPLANTED SALVAGED SHRUBS	EACH	10	10					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	184	184					
28000510	INLET FILTERS	EACH	164	164					
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	8129	8129					
35300405	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/4"	SQ YD	394	394					
35300515	PORTLAND CEMENT CONCRETE BASE COURSE 10 3/4"	SQ YD	4190	4190					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6142	6142					
40600300	AGGREGATE (PRIME COAT)	TON	61	61					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL -- BUTT JOINT	SQ YD	293	293					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4486	4486					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1779	1779					

● SPECIALTY ITEM

FILE NAME = J:\2275\Cad\Sheet\2275_Sum_Quant.dgn	USER NAME = djc	DESIGNED - JAT	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 50.0000' / IN.	CHECKED - DJK	REVISIONS -	2743			05-00161-00-CH	COOK	112	4	
PLOT DATE = 12/11/2009	DATE - 11-23-09	REVISIONS -	CONTRACT NO. 63383							
			SHEET NO. 1 OF 9 SHEETS			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CMM-M-8003(543)				