

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	J000-2A	SFTY-1B	SFTY-1B	Y031-1F	Y031-1F	Y040
				ROADWAY	SIDEWALK (STA. 113+74 TO STA. 118+85, RT)	SIDEWALK (STA. 98+39 TO STA. 107+87)	TRAFFIC SIGNALS	EMERGENCY VEHICLE PRE-EMPTION	WATERMAIN
				70% FEDERAL / 30% VILLAGE	80% FEDERAL / 20% VILLAGE	80% FEDERAL / 20% VILLAGE	70% FEDERAL / 30% VILLAGE	100% VILLAGE	100% VILLAGE
● 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	426				426		
● 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	17				17		
● 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	6				6		
● 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	405				405		
● 81400100	HANDHOLE	EACH	4				4		
● 81400200	HEAVY-DUTY HANDHOLE	EACH	4				4		
● 81400300	DOUBLE HANDHOLE	EACH	2				2		
● 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	562				562		
● 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1				1		
● 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1256				1256		
● 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1629				1629		
● 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	793				793		
● 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2127				2127		
● 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1928				1928		
● 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	150				150		
● 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4				4		
● 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1				1		
● 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1				1		
● 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2				2		
● 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16				16		
● 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4				4		
● 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	52				52		
● 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4				4		
● 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2		
● 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6				6		
● 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2				2		
● 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8				8		
● 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10				10		
● 88500100	INDUCTIVE LOOP DETECTOR	EACH	10				10		
● 88600100	DETECTOR LOOP, TYPE 1	FOOT	1265				1265		
● 88700200	LIGHT DETECTOR	EACH	2					2	

● SPECIALTY ITEM

FILE NAME = J:\2275\Cad\Sheet\2275_Sum_Quant.dgn	USER NAME = djk	DESIGNED - JAT	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.U. RTE. 2743	SECTION 05-00161-00-CH	COUNTY COOK	TOTAL SHEETS 112	SHEET NO. 9		
PLOT SCALE = 50.0000' / IN.	CHECKED - DJK	REVISED -	SHEET NO. 6 OF 9 SHEETS			CONTRACT NO. 63383						
PLOT DATE = 12/11/2009	DATE - 11-23-09	REVISED -	FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT CMM-M-8003543									