


ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	LINCOLNSHIRE IRRIGATION AND LANDSCAPING
							I000-2A	Y030-1E	
1		*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	237	237		
2			20101000	TEMPORARY FENCE	FOOT	407	407		
3		*	20101100	TREE TRUNK PROTECTION	EACH	46	46		
4	+	*	20101200	TREE ROOT PRUNING	EACH	50	50		
5	+		20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	25	25		
6	+		20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25		
7			20200100	EARTH EXCAVATION	CU YD	5,481	5,481		
8			20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7,645	7,645		
9		*	20400800	FURNISHED EXCAVATION	CU YD	5,197	5,197		
10		*	20700300	POROUS GRANULAR EMBANKMENT, SPECIAL	TON	5,008	5,008		
11		*	20800250	TRENCH BACKFILL, SPECIAL	CU YD	870	870		
12			21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	10,516	10,516		
13	+	*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7,817	7,817		
14	+		25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75		
15	+		25000312	SEEDING, CLASS 4A	ACRE	2	2		
16	+		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	250	250		
17	+		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	250	250		
18	+		25100630	EROSION CONTROL BLANKET	SQ YD	13,749	13,749		
19	+	*	25400105	PERENNIAL PLANTS	EACH	3,829	3,829		
20	+		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	284	284		
21		*	28000305	TEMPORARY DITCH CHECKS	FOOT	938	938		
22		*	28000400	PERIMETER EROSION BARRIER	FOOT	5,720	5,720		
23			28000510	INLET FILTERS	EACH	8	8		
24			28100105	STONE RIPRAP, CLASS A3	SQ YD	144	144		
25			28200200	FILTER FABRIC	SQ YD	144	144		
26		*	35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	690	690		
27		*	35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	136	136		
28		*	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20		
29		*	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,133	1,133		
30			40600300	AGGREGATE (PRIME COAT)	TON	40	40		
31			40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	91	91		
32			40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	61	61		
33			40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,740	2,740		
34			40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	TON	1,022	1,022		
35			42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	493	493		
36		*	42001300	PROTECTIVE COAT	SQ YD	3,094	3,094		
37			42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	6,201	6,201		
38		*	42400800	DETECTABLE WARNINGS	SQ FT	274	274		
39			44000100	PAVEMENT REMOVAL	SQ YD	13,682	13,682		
40		*	44000180	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	2,267	2,267		
41			44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	50	50		
42			44000600	SIDEWALK REMOVAL	SQ FT	3,395	3,395		

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	LINCOLNSHIRE IRRIGATION AND LANDSCAPING
							I000-2A	Y030-1E	
43			48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	1,113	1,113		
44			50105220	PIPE CULVERT REMOVAL	FOOT	2,209	2,209		
45			54213857	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4		
46			54213680	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	6		
47			54213683	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	8	8		
48			X0321583	PIPE ELBOW 18"	EACH	2	2		
49		*	55038400	STORM SEWERS TO BE CLEANED 30"	FOOT	885	885		
50			55100500	STORM SEWER REMOVAL 12"	FOOT	15	15		
51			55100900	STORM SEWER REMOVAL 18"	FOOT	62	62		
52			55101400	STORM SEWER REMOVAL 30"	FOOT	13	13		
53			56200700	WATER SERVICE LINE 2"	FOOT	1,406	1,406		
54			59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	11	11		
55			60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1		
56			60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2		
57			60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	3	3		
58			60208240	CATCH BASIN, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1		
59			60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60			60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
61			60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1		
62			60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1		
63			60255500	MANHOLES TO BE ADJUSTED	EACH	4	4		
64			60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1		
65			60500040	REMOVING MANHOLES	EACH	1	1		
66		*	60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	2,076	2,076		
67			60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,211	2,211		
68		*	60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	681	681		
69		*	60605400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL)	FOOT	245	245		
70		*	60606600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL)	FOOT	352	352		
71			60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3,878	3,878		
72	+		66500105	WOVEN WIRE FENCE, 4'	FOOT	992	992		
73			66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	12	12		
74			67100100	MOBILIZATION	L SUM	1	1		
75		*	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
76			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	32	32		
77			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,500	2,500		
78			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,849	20,849		
79			70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	21,097	21,097		
80			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	333	333		
81			70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2,500	2,500		
82			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11,120	11,120		
83			70400100	TEMPORARY CONCRETE BARRIER	FOOT	80	80		
84	+		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	160	160		
85	+		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,784	2,784		

* DENOTES SPECIALTY PROVISION. + DENOTES SPECIALTY ITEM.

REVISIONS / REMARKS		DATE	BY	DESIGNED BY:	JRM
NO.	DESCRIPTION	/ /	/	CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010



SUMMARY OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	4	107

63415