

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	LINCOLNSHIRE IRRIGATION AND LANDSCAPING
							I000-2A	Y030-1E	
86	+		78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	823	823		
87	+		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	172	172		
88	+		78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2,189	2,189		
89	+		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220		
90	+		78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,024	3,024		
91	+		78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	5,955	5,955		
92	+	*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	116	116		
93	+		80400100	ELECTRIC SERVICE INSTALLATION	EACH	2		1	1
94	+	*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1	
95	+		81000100	CONDUIT IN TRENCH, 1/2" DIA., GALVANIZED STEEL	FOOT	100			100
96	+		81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	350			350
97	+		81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	200		100	100
98	+		81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	305		305	
99	+		81018200	CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	135			135
100	+		81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	330		330	
101	+		81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	330		330	
102	+		81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	20		20	
103	+		81603185	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 6 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE	FOOT	2,870		2,870	
104	+		81700105	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 12	FOOT	300			300
105	+		81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1,845		945	900
106	+		81700120	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 6	FOOT	25		25	
107	+		81701315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO.2	FOOT	800		300	300
108	+		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,555		2,320	235
109	+		82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	18		18	
110	+		82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	2		2	
111	+		82500350	LIGHTING CONTROLLER, Base Mounted, 240V, 100Amp	EACH	2		1	1
112	+		83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	140		140	
113			542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	96	96		
114			542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	2,046	2,046		
115			550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	208	208		
116			550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	186	186		
117	+	*	A2008453	TREE, ULMUS ACCOLADE, (HYBRID ELM), 3" CALIPER, BALLED AND BURLAPPED	EACH	12	12		
118	+	*	C2C00724	SHRUB, BERBERIS THUNBERGII (JAPANESE BARBERRY), 2' HEIGHT, CONTAINER	EACH	460	460		
119	+	*	C2C073G3	SHRUB, ROSA RUGOSA DWARF PAVEMENT (DWARF PAVEMENT ROSE), CONTAINER GROWN 3-GALLON	EACH	1,220	1,220		
120	+	*	C2C078G3	SHRUB, ROSA X KNOCK OUT (KNOCK OUT ROSE), CONTAINER GROWN, 3-GALLON	EACH	840	840		
121	+	*	C2010324	SHRUB, SPIREA NIPPONICA SNOWMOUND (SNOWMOUND SPIREA), 2' HEIGHT, BALLED AND BURLAPPED NIPPON	EACH	120	120		
122	+	*	K0030401	PERENNIAL PLANTS, CALAMAGROSTIS ACUTIFOLIA KARL FORSTER (FEATHER REED GRASS), 1-GALLON	EACH	992	992		
123	+	*	K1003680	MULCH	SQ YD	31	31		
124	+	*	X0322494	CURB CUT	FOOT	85	85		

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	LINCOLNSHIRE IRRIGATION AND LANDSCAPING
							I000-2A	Y030-1E	
125	+	*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6		6	
126	+	*	X0324597	CLOSED CIRCUIT TELEVISION CABINET	EACH	1		1	
127		*	X0325055	CONCRETE MEDIAN SURFACE, (STAMPING)	SQ FT	5,962	5,962		
128	+	*	X0325810	WIRELESS ETHERNET RADIO	EACH	1		1	
129	+	*	X0326756	LIGHT POLE, COMPLETE IN PLACE, TYPE 1	EACH	18		18	
130	+	*	X0326757	LIGHT POLE, COMPLETE IN PLACE, TYPE 2	EACH	2		2	
131	+	*	X0326812	CAT 5 ETHERNET CABLE	FOOT	60		60	
132		*	X0712400	TEMPORARY PAVEMENT	SQ YD	7,235	7,235		
133	+	*	X2800500	INLET PROTECTION, SPECIAL	EACH	13	13		
134		*	X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	4,071	4,071		
135		*	X6700405	ENGINEER'S FIELD OFFICE, TYPE A (MODIFIED)	CAL MO	8	8		
136		*	X0003487	CURB BOX	EACH	1	1		
137	+	*	XX003710	BACKFLOW PREVENTER, 2"	EACH	1	1		
138	+	*	XX003885	IRRIGATION SYSTEM	L SUM	1	1		
139		*	XX004878	MAINTENANCE OF TEMPORARY EROSION CONTROL SYSTEMS	L SUM	1	1		
140		*	XX005642	GATEWAY MONUMENT SIGN COMPLETE	EACH	4	4		
141	+	*	XX005940	REMOTE CONTROLLED VIDEO SYSTEM	EACH	1		1	
142	+	*	XX006338	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	7,000	7,000		
143	+	*	XX006570	TREES (SPECIAL)	EACH	17	17		
144	+	*	XX007343	MULCH, SHREDDED HARDWOOD, 4"	SQ YD	79	79		
145	+	*	XX007469	UPLIGHTS	EACH	8			8
146		*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	10,015	10,015		
147		*	Z0015300	CURB STOPS 2"	EACH	1	1		
148		*	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4		
149		*	Z0019600	DUST CONTROL WATERING	UNIT	48	48		
150		*	Z0022600	FENCE REMOVAL	FOOT	955	955		
151		*	Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	4	4		
152	+	*	Z0038200	PAINT CURB	FOOT	1,960	1,960		
153		*	Z0042450	SAWING Pavement (full depth)	FOOT	1,000	1,000		
154		*	Z0078600	TRAINEES	HOUR	500	500		

Δ Y080

63415

+ DENOTES SPECIALTY ITEM. * DENOTES SPECIALTY PROVISION.

NO.	REVISIONS / REMARKS	DATE	BY	DESIGNED BY:	JRM
	DESCRIPTION	/ /		CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010

HDR 38 N LaSalle Street, Suite 3220
Chicago, IL 60682
312-443-4900
HDR Engineering, Inc.

Lake County
Division of Transportation

SUMMARY OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	5	107