

10 SCHEDULE OF TEMPORARY EROSION CONTROL SEEDING (28000250)					
FROM	TO	OFFSET	AREA (SQ FT)	AREA (ACRE)	WEIGHT (POUND)
RIVERWOODS ROAD STAGE 1					
3355+65	3358+38	RT	2038.8	0.0	5
3357+80	3359+02	RT	989.6	0.0	2
3358+64	3359+33	LT	1160	0.0	3
3359+76	3361+61	RT	11306.6	0.3	26
3361+61	85+89	RT	5712.1	0.1	13
SUBTOTAL					49
RIVERWOODS ROAD STAGE 2-4					
3353+00	3358+64	LT	8514.5	0.2	20
3353+00	3358+70	RT	6640.2	0.2	15
3358+64	3359+33	LT	1160	0.0	3
3360+21	3361+58	RT	3279.6	0.1	8
3360+87	3365+40	LT	7337.4	0.2	17
3360+94	3365+40	RT	2709.1	0.1	6
3365+40	85+89	RT	3250.3	0.1	7
SUBTOTAL					76
EVERETT ROAD STAGE 1					
101+41	3280+10	RT	10370.9	0.2	24
3281+38	9+45	RT	12686.8	0.3	29
SUBTOTAL					53
EVERETT ROAD STAGE 2-4					
101+41	3280+10	RT	10370.9	0.2	24
3273+90	3278+27	LT	7094.3	0.2	16
3276+71	3280+49	LT	6128.1	0.1	14
3281+38	9+45	RT	12686.8	0.3	29
3282+00	3285+00	LT	3484.7	0.1	8
3282+24	3286+51	LT	6822.4	0.2	16
SUBTOTAL					107
PROJECT TOTAL					284

13 SCHEDULE OF STONE RIPRAP, CLASS A3 (28100105)						
STRUCTURE #	PIPE DIA. (IN)	STATION (FT)	OFFSET (FT)	LT/RT	GRADATION	QTY (SQ YD)
EVERETT ROAD						
3	18	3280+01.40	59.01	RT	RR3	9
T1	18	120+19.38	20.85	RT	RR3	9
T2	18	102+19.39	25.35	RT	RR3	9
RIVERWOODS ROAD						
6	18	3358+53.47	37.00	LT	RR3	9
13	18	3358+05.00	32.80	RT	RR3	9
T5	18	3358+87.20	33.74	LT	RR3	9
T6	18	3358+89.98	27.10	LT	RR3	9
T7	18	3358+89.98	27.10	LT	RR3	9
20	12	3282+26.00	36.50	LT	RR3	6
21	12	3282+38.00	36.00	LT	RR3	6
24	12	3284+05.69	36.38	LT	RR3	6
T8	12	3281+28.03	52.25	LT	RR3	6
25	15	3362+73.00	35.20	LT	RR3	8
26	15	3360+10.00	35.20	LT	RR3	8
27	15	3363+67.00	34.70	LT	RR3	8
28	15	3364+05.00	34.70	LT	RR3	8
29	15	3364+29.00	34.00	LT	RR3	8
30	15	3364+67.00	33.00	RT	RR3	8
PROJECT TOTAL						144


11 SCHEDULE OF PERIMETER EROSION BARRIER (28000400)			
FROM	TO	OFFSET	LENGTH (FT)
RIVERWOODS ROAD STAGE 1			
3355+65	3357+80	RT	215
3359+97	3364+00	RT	466
SUBTOTAL			681
RIVERWOODS ROAD STAGE 2-4			
3353+00	3357+80	RT	484
3353+00	3358+85	LT	586
3359+97	3364+00	RT	466
SUBTOTAL			1536
EVERETT ROAD STAGE 1			
101+41	3280+40	RT	1046
3281+49	3284+00	RT	370
SUBTOTAL			1416
EVERETT ROAD STAGE 2-4			
101+41	3280+40	RT	1023
3273+90	3280+51	LT	694
3281+49	3284+00	RT	370
SUBTOTAL			2087
PROJECT TOTAL			5720

12 SCHEDULE OF INLET FILTERS (28000510)		
STA	OFFSET	EACH
RIVERWOODS ROAD STAGE 2-4		
3358+92	LT	1
3358+92	RT	1
SUBTOTAL		2
EVERETT ROAD STAGE 2-4		
3281+56	RT	1
3281+72	LT	1
3281+73	RT	1
3281+90	RT	1
3282+32	RT	1
3284+07	RT	1
SUBTOTAL		6
PROJECT TOTAL		8

14 SCHEDULE OF FILTER FABRIC (28200200)						
STRUCTURE #	PIPE DIA. (IN)	STATION (FT)	OFFSET (FT)	LT/RT	GRADATION	QTY (SQ YD)
EVERETT ROAD						
3	18	3280+01.40	59.01	RT	RR3	9
T1	18	120+19.38	20.85	RT	RR3	9
T2	18	102+19.39	25.35	RT	RR3	9
RIVERWOODS ROAD						
6	18	3358+53.47	37.00	LT	RR3	9
13	18	3358+05.00	32.80	RT	RR3	9
T5	18	3358+87.20	33.74	LT	RR3	9
T6	18	3358+89.98	27.10	LT	RR3	9
T7	18	3358+89.98	27.10	LT	RR3	9
20	12	3282+26.00	36.50	LT	RR3	6
21	12	3282+38.00	36.00	LT	RR3	6
24	12	3284+05.69	36.38	LT	RR3	6
T8	12	3281+28.03	52.25	LT	RR3	6
25	15	3362+73.00	35.20	LT	RR3	8
26	15	3360+10.00	35.20	LT	RR3	8
27	15	3363+67.00	34.70	LT	RR3	8
28	15	3364+05.00	34.70	LT	RR3	8
29	15	3364+29.00	34.00	LT	RR3	8
30	15	3364+67.00	33.00	RT	RR3	8
PROJECT TOTAL						144

REVISIONS / REMARKS					
NO.	DESCRIPTION	DATE	BY	DESIGNED BY:	JRM
		/ /		CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010

FILE NAME:



SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	8	107

603415