

**23 SUMMARY OF PROTECTIVE COAT (42001300)**

|  | LENGTH (FT) | WIDTH (FT) | AREA (SQ FT)  | AREA (SQ YD) |
|--|-------------|------------|---------------|--------------|
| ROUNDBABOUT  |             |            |               |              |
|  |             |            | 4440.34       | 493          |
| SIDEWALK   |             |            |               |              |
|  |             |            | 5579          | 620          |
| COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12                              |             |            |               |              |
|  | 2046        | 2.1        | 4296.6        | 478          |
| COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24                              |             |            |               |              |
|  | 2446        | 4.1        | 10028.6       | 1115         |
| COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT) |             |            |               |              |
|  | 680         | 4.1        | 2788          | 310          |
| COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12                              |             |            |               |              |
|  | 348         | 2          | 696           | 78           |
|  |             |            | SUBTOTAL      | 3094         |
|  |             |            | PROJECT TOTAL | 3094         |

NOTE: TOTAL QUANTITY IS THE AREA FOR ONE (1) APPLICATION, BUT THE UNIT PRICE SHALL INCLUDE SECOND APPLICATION WITH NO ADDITIONAL COMPENSATION.

**24 SUMMARY OF PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (42400200)**

|  | SQ FT         |
|--|---------------|
| RIVERWOODS ROAD/EVERETT ROAD ROUNDBABOUT |               |
| NW corner of intersection                | 1149.60       |
| NE corner of intersection                | 1683.78       |
| SW corner of intersection                | 686.95        |
| SE corner of intersection                | 2058.12       |
| South Leg                                | 607.50        |
| Backflow Preventer Foundation            | 15.00         |
|  | SUBTOTAL      |
|  | 6200.9        |
|  | PROJECT TOTAL |
|  | 6201          |

**25 SCHEDULE OF DETECTABLE WARNINGS (42400800)**

| STATION         | OFFSET          | SQ FT |
|-----------------|-----------------|-------|
| RIVERWOODS ROAD |                 |       |
| 3358+78         | LT              | 12    |
| 3358+78         | RT              | 20    |
| 3358+78         | SPLITTER ISLAND | 16    |
| 3358+78         | SPLITTER ISLAND | 16    |
| 3360+89         | LT              | 20    |
| 3360+89         | RT              | 20    |
| 3360+89         | SPLITTER ISLAND | 16    |
| 3360+89         | SPLITTER ISLAND | 16    |
|                 | SUBTOTAL        | 136   |
| EVERETT ROAD    |                 |       |
| 3279+84         | LT              | 20    |
| 3279+84         | RT              | 12    |
| 3279+84         | SPLITTER ISLAND | 16    |
| 3279+84         | SPLITTER ISLAND | 16    |
| 3281+95         | LT              | 20    |
| 3281+95         | RT              | 22    |
| 3281+95         | SPLITTER ISLAND | 16    |
| 3281+95         | SPLITTER ISLAND | 16    |
|                 | SUBTOTAL        | 138   |
|                 | PROJECT TOTAL   | 274   |

**26 SCHEDULE OF PAVEMENT REMOVAL (44000100)**

| FROM            | TO               | AREA (SQ FT) | AREA (SQ YD) |
|-----------------|------------------|--------------|--------------|
| RIVERWOODS ROAD |                  |              |              |
| 3356+40         | 3359+00          | 8310.3       | 923          |
| 3361+00         | 3364+27          | 9211.2       | 1023         |
|                 | SUBTOTAL         |              | 1947         |
| EVERETT ROAD    |                  |              |              |
| 3274+40         | 3280+00          | 15729.6      | 1748         |
| 3282+00         | 3286+04          | 11594.1      | 1288         |
|                 | SUBTOTAL         |              | 3036         |
| INTERSECTION    |                  |              |              |
| 3280+00         | 3282+00          | 13180.6      | 1465         |
| IRRIGATION      |                  |              |              |
|                 |                  | 1966         | 218          |
| STAGE 1         |                  |              |              |
| EVERETT ROAD    |                  |              |              |
| 3269+97         | 3280+52          | 14512        | 1612         |
| 3282+00         | 3290+32          | 16417        | 1824         |
| RIVERWOODS ROAD |                  |              |              |
| 3355+70         | 3359+43          | 6392         | 710          |
| 3359+74         | 3367+24          | 13327        | 1481         |
|                 | STAGE 1 SUBTOTAL |              | 5628         |
| STAGE 2         |                  |              |              |
| EVERETT ROAD    |                  |              |              |
| 3277+71         | 3279+79          | 2699         | 300          |
| 3279+87         | 3280+14          | 589          | 65           |
| 3280+36         | 3280+67          | 1449         | 161          |
| 3281+65         | 3281+92          | 448          | 50           |
| 3282+00         | 3284+09          | 2313         | 257          |
|                 | STAGE 2 SUBTOTAL |              | 833          |
| STAGE 3         |                  |              |              |
| RIVERWOODS ROAD |                  |              |              |
| 3356+46         | 3356+74          | 2269         | 252          |
| 3358+82         | 3358+09          | 432          | 48           |
| 3360+59         | 3360+86          | 500          | 56           |
| 3360+93         | 3360+94          | 1798         | 200          |
|                 | STAGE 3 SUBTOTAL |              | 555          |
|                 | SUBTOTAL         |              | 13682        |
|                 | PROJECT TOTAL    |              | 13682        |

**27 SCHEDULE OF HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4" (44000160)**

| FROM            | TO            | AREA (SQ FT) | AREA (SQ YD) |
|-----------------|---------------|--------------|--------------|
| RIVERWOODS ROAD |               |              |              |
| 3353+00         | 3356+40       | 14409.3      | 1601         |
| 3364+27         | 3365+40       | 3236.2       | 360          |
|                 | SUBTOTAL      |              | 1961         |
| EVERETT ROAD    |               |              |              |
| 3273+90         | 3274+40       | 1408.1       | 156          |
| 3286+04         | 3286+51       | 1347.9       | 150          |
|                 | SUBTOTAL      |              | 306          |
|                 | PROJECT TOTAL |              | 2267         |

**28 SCHEDULE OF COMBINATION CURB AND GUTTER REMOVAL (44000500)**

| FROM            | TO            | LENGTH (FOOT) |
|-----------------|---------------|---------------|
| RIVERWOODS ROAD |               |               |
| 3353+00         | 3353+24       | 24            |
| 3353+00         | 3353+26       | 26            |
|                 | SUBTOTAL      | 50            |
|                 | PROJECT TOTAL | 50            |

**29 SCHEDULE OF SIDEWALK REMOVAL (44000600)**

| FROM            | TO            | AREA (SQ FT) |
|-----------------|---------------|--------------|
| RIVERWOODS ROAD |               |              |
| 3357+80         | 3359+32       | 1490         |
| 71+43           | 3353+38       | 608          |
|                 | SUBTOTAL      | 2098         |
| EVERETT ROAD    |               |              |
| 3281+13         | 3282+27       | 1297         |
|                 | SUBTOTAL      | 1297         |
|                 | PROJECT TOTAL | 3395         |

**30 SCHEDULE OF AGGREGATE SHOULDERS, TYPE A 6" (48100500)**


| LOCATION      | FROM STATION | TO STATION | RT/LT         | SURFACE AREA |         |
|---------------|--------------|------------|---------------|--------------|---------|
|               |              |            |               | SQ FT        | (SQ YD) |
| RIVERWOODS RD | 3362+66.01   | 3362+83.12 | LT            | 70.6         | 8       |
| RIVERWOODS RD | 3362+99.12   | 3363+77.05 | LT            | 451.5        | 51      |
| RIVERWOODS RD | 3363+93.00   | 3365+40.00 | LT            | 919.2        | 103     |
| RIVERWOODS RD | 3363+06.00   | 3364+39.34 | RT            | 769.5        | 86      |
| RIVERWOODS RD | 3364+57.35   | 3365+40.00 | RT            | 597.4        | 67      |
| EVERETT RD    | 3273+90.00   | 3277+65.18 | LT            | 2198.1       | 245     |
| EVERETT RD    | 3273+90.00   | 3277+64.71 | RT            | 2198.4       | 245     |
| EVERETT RD    | 3284+15.34   | 3286+51.41 | LT            | 1373.5       | 153     |
| EVERETT RD    | 3284+15.19   | 3286+51.41 | RT            | 1394.8       | 155     |
|               |              |            | PROJECT TOTAL |              | 1113    |

**31 SCHEDULE OF PIPE CULVERT REMOVAL (50105220)**

| FROM            | TO      | LOCATION      | DIA (IN) | LENGTH (FOOT) |
|-----------------|---------|---------------|----------|---------------|
| RIVERWOODS ROAD |         |               |          |               |
| 3357+50         | 3358+87 | RT            | 18       | 149           |
| 3362+74         | 3363+04 | LT            | 15       | 41            |
| 3363+70         | 3363+99 | LT            | 15       | 41            |
| 3364+33         | 3364+62 | RT            | 15       | 41            |
| EVERETT ROAD    |         |               |          |               |
| 3273+83         | 3280+68 | RT            | 18       | 972           |
| 3273+83         | 3280+60 | RT            | 18       | 964           |
|                 |         | SUBTOTAL      |          | 2208          |
|                 |         | PROJECT TOTAL |          | 2209          |

63415

| REVISIONS / REMARKS |             |      |    |              |           |
|---------------------|-------------|------|----|--------------|-----------|
| NO.                 | DESCRIPTION | DATE | BY | DESIGNED BY: | JRM       |
|                     |             |      |    |              |           |
|                     |             |      |    | CHECKED BY:  | MPK/JLC   |
|                     |             |      |    | DATE:        | 1/22/2010 |



SCHEDULE OF QUANTITIES

| ROUTE | SECTION | SECTION NUMBER | SHEET | SHEETS |
|-------|---------|----------------|-------|--------|
| CH    | 136     | 04-00136-06-CH | 10    | 107    |