

32 SCHEDULE OF PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" (54213657)

STRUCTURE #	STATION	LOCATION	EACH
EVERETT ROAD			
20	3282+26	36.50, LT	1
21	3282+38	36.00, LT	1
24	3284+06	36.38, LT	1
T8	3281+28	52.25, LT	1
PROJECT TOTAL			4

33 SCHEDULE OF PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15" (54213660)

STRUCTURE #	STATION	LOCATION	EACH
EVERETT ROAD			
25	3362+73	35.20, LT	1
26	3360+10	35.20, LT	1
27	3363+67	34.70, LT	1
28	3364+05	34.70, LT	1
29	3364+29	34.00, LT	1
30	3364+67	33.00, RT	1
PROJECT TOTAL			6

34 SCHEDULE OF PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" (54213663)

STRUCTURE #	STATION	LOCATION	EACH
EVERETT ROAD			
3	3280+01	59.01, RT	1
RIVERWOODS ROAD			
6	3358+53	37.00, LT	1
13	3358+05	32.80, RT	1
T5	3358+87	33.74, LT	1
T6	3358+90	27.10, LT	1
T7	3358+90	27.10, LT	1
INTERSECTION			
T1	120+19	20.85, RT	1
T2	102+19	25.35, RT	1
PROJECT TOTAL			8

35 SCHEDULE OF REINFORCED CONCRETE PIPE ELBOW 18" (54213663)

STRUCTURE #	STATION	LOCATION	EACH
EVERETT ROAD			
T3	3280+42.54	59.55 RT	1
T4	3280+36.06	64.12 RT	1
PROJECT TOTAL			2

36 SCHEDULE OF PIPE CULVERTS, CLASS A, TYPE 1 15" (542A0220)

STRUCTURE I.D.			
STRUCTURE #	FROM	TO	LENGTH (FOOT)
12	25	26	32
13	27	28	32
14	29	30	32
SUBTOTAL			96
PROJECT TOTAL			96

37 SCHEDULE OF PIPE CULVERTS, CLASS C, TYPE 1 18" (542C0223)

STRUCTURE I.D.			
PIPE #	FROM	TO	LENGTH (FOOT)
TP1	TP1	TP3	916
TP2	TP2	TP4	914
TP3	TP3	TP5 & 5	36
TP4	TP4	TP6 & 7	44
TP5	TP7	EXIST	136
SUBTOTAL			2046
PROJECT TOTAL			2046

38 SCHEDULE OF STORM SEWERS TO BE CLEANED, 30" (55038400)

STRUCTURE I.D.		
FROM	TO	LENGTH (FOOT)
7	11	36
11	14	56
14	EX MH, STA 3285+44, 19' RT, EVERETT RD	393
EX MH, STA 3285+44, 19' RT, EVERETT RD	EX MH, STA 3633+66, 20' RT, EVERETT RD	399
SUBTOTAL		885
PROJECT TOTAL		885

39 SCHEDULE OF STORM SEWER REMOVAL 12" (55100500)

FROM	TO	LOCATION	LENGTH (FOOT)
RIVERWOODS ROAD			
-	3360+24	RT	15
SUBTOTAL			15
PROJECT TOTAL			15

40 SCHEDULE OF STORM SEWER REMOVAL 18" (55100900)

FROM	TO	LOCATION	LENGTH (FOOT)
RIVERWOODS ROAD			
-	3358+88	RT	9
-	3360+25	34' LT - 13' RT	53
SUBTOTAL			61
PROJECT TOTAL			62

41 SCHEDULE OF STORM SEWER REMOVAL 30" (55101400)


FROM	TO	LOCATION	LENGTH (FOOT)
RIVERWOODS ROAD			
-	3358+85	LT	13
SUBTOTAL			13
PROJECT TOTAL			13

42 SCHEDULE OF STORM SEWERS, CLASS A, TYPE 1 12" (550A0050)

STRUCTURE I.D.			
PIPE #	FROM	TO	LENGTH (FOOT)
5	15	14	40
6	18	17	24
7	22	17	56
8	19	20	38
11	23	24	34
TP6	TP8	EXISTING	16
SUBTOTAL			208
PROJECT TOTAL			208

REVISIONS / REMARKS					
NO.	DESCRIPTION	DATE	BY	DESIGNED BY:	JRM
				CHECKED BY:	MPK/JLC
				DATE:	1/22/2010

FILE NAME:



SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	11	107

63415