

43 SCHEDULE OF STORM SEWERS, CLASS A, TYPE 1 18" (550A0090)

STRUCTURE I.D.			
PIPE #	FROM	TO	LENGTH (FOOT)
1	3	4	28
2	4	5	28
3	6	5	28
4	13	12	80
4a	12	11	10
9	17	16	4
10	5	7	8
SUBTOTAL			186
PROJECT TOTAL			186

48 SCHEDULE OF CATCH BASIN, TYPE C, TYPE 24 FRAME AND GRATE (60208240)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
19	3281+81	30.05' LT	1
PROJECT TOTAL			1

49 SCHEDULE OF MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (60218400)

STRUCTURE #	STATION	LOCATION	EACH
RIVERWOODS ROAD			
4	3359+15	50.67' LT	1
PROJECT TOTAL			1

50 SCHEDULE OF MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID (60221100)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
16	3281+80	37.28' RT	1
RIVERWOODS ROAD			
7	3358+85	24.63' LT	1
PROJECT TOTAL			2

44 SCHEDULE OF CONTROLLED LOW STRENGTH MATERIAL (59300100)

LOCATION	STATION	DIA (IN) (IN)	LENGTH (FT)	VOLUME (CU YD)
EVERETT RD	3281+25	24	94	11
TOTAL				11 CU YD

51 SCHEDULE OF INLETS, TYPE A, TYPE 11 FRAME AND GRATE (60236800)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
18	3281+89	7.36' RT	1
PROJECT TOTAL			1

45 SCHEDULE OF CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE (60201340)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
17	3281+82	32.52' RT	1
PROJECT TOTAL			1

52 SCHEDULE OF CATCH BASINS TO BE RECONSTRUCTED (60252800)

STRUCTURE #	STATION	LOCATION	EACH
RIVERWOODS ROAD			
5	3358+89	32.77' LT	1
PROJECT TOTAL			1

46 SCHEDULE OF CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE (60205040)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
12	3358+87	26.91' RT	1
RIVERWOODS ROAD			
5	3358+89	33.59' LT	1
PROJECT TOTAL			2

53 SCHEDULE OF MANHOLES TO BE ADJUSTED (60255500)

STRUCTURE #	STATION	LOCATION	EACH
RIVERWOODS ROAD			
11	3358+89	15.79' RT	2
ROUNDBABOUT			
14	102+16	16.55' LT	2
PROJECT TOTAL			4

47 SCHEDULE OF CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE (60207905)

STRUCTURE #	STATION	OFFSET	EACH
EVERETT ROAD			
22	3282+30	6.00' RT	1
23	3284+05	5.06' RT	1
ROUNDBABOUT			
15	101+85	20.78' LT	1
PROJECT TOTAL			3

54 SCHEDULE OF MANHOLES TO BE RECONSTRUCTED (60257900)

STRUCTURE #	STATION	OFFSET	EACH
RIVERWOODS ROAD			
7	3358+85	24.63' LT	1
PROJECT TOTAL			1

63415

REVISIONS / REMARKS				
NO.	DESCRIPTION	DATE	BY	DESIGNED BY:
		/ /		JRM
		/ /		MPK/JLC
		/ /		DATE: 1/22/2010

**HDR** 38 N LaSalle Street, Suite 3220  
Chicago, IL 60682  
312-443-4900  
HDR Engineering, Inc.

**LakeCounty**  
Division of Transportation

SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	12	107

FILE NAME: