

55 SCHEDULE OF REMOVING MANHOLES (60500040)

STATION	OFFSET	EACH
RIVERWOODS ROAD		
3360+23	15.40' RT	1
PROJECT TOTAL		1

56 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL) (60604200)

	LENGTH (FOOT)	
medians, north of intersection	500.30	
medians, south of intersection	548.79	
medians, west of intersection	520.29	
medians, east of intersection	505.87	
SUBTOTAL		2075.26
PROJECT TOTAL		2076

57 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (60605000)

	LENGTH (FOOT)	
northwest of intersection	511.02	
northeast of intersection	560.88	
southwest of intersection	569.35	
southeast of intersection	569.04	
SUBTOTAL		2210.29
PROJECT TOTAL		2211

58 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT) (60605100)

FROM	TO	LOCATION	LENGTH (FOOT)
RIVERWOODS ROAD			
3353+00	3356+40	RT	339.41
3353+00	3356+40	LT	340.62
SUBTOTAL			680.02
PROJECT TOTAL			681

59 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (SPECIAL) (60605400)

	LENGTH (FOOT)	
roundabout	244.68	
SUBTOTAL		244.68
PROJECT TOTAL		245

60 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL) (60609600)

	LENGTH (FOOT)	
roundabout	351.86	
SUBTOTAL		351.86
PROJECT TOTAL		352

61 SCHEDULE OF CONCRETE MEDIAN SURFACE, 4 INCH (60618300)

STATION	SQ. FT.	
RIVERWOODS ROAD		
3358+15	801	
3359+00	343	
3360+75	417	
3361+49	506	
SUBTOTAL		2067
EVERETT ROAD		
3279+18	524	
3280+00	444	
3281+75	321	
3282+58	522	
SUBTOTAL		1811
PROJECT TOTAL		3878

62 SCHEDULE OF PIPE WOVEN WIRE FENCE, 4'

FROM STA	TO STA	OFFSET	FOOT
RIVERWOODS ROAD			
3360+20	3361+73	RT	216
SUBTOTAL			216
EVERETT ROAD			
3275+55	3280+40	LT	526
3282+51	3284+98	LT	250
SUBTOTAL			776
PROJECT TOTAL			992

63 SCHEDULE OF CHANGEABLE MESSAGE SIGN

STATION	CAL MO	
RIVERWOODS ROAD		
33+53	8	
66+66	8	
EVERETT ROAD		
96+00	8	
14+45	8	
PROJECT TOTAL		32

64 SCHEDULE OF TEMPORARY PAVEMENT MARKING LINE - 4" (70300220)

FROM	TO	DIRECTION	LENGTH (FOOT)
STAGE 2 - RIVERWOODS ROAD			
3354+93	3358+93	CL	801
3360+16	3367+40	CL	1449
STAGE 2 - EVERETT ROAD			
3269+88	3280+43	CL	2111
3281+76	3290+48	CL	1744
STAGE 3 - RIVERWOODS ROAD			
3355+66	3359+09	SB	343
3354+93	3359+07	NB	414
3360+28	3365+67	SB	538
3360+25	3367+40	NB	715
STAGE 3 - EVERETT ROAD			
3269+87	3280+55	EB	1067
3273+56	3280+46	WB	690
3281+44	3290+48	EB	904
3281+56	3287+43	WB	587
STAGE 4 - RIVERWOODS ROAD			
3354+00	3359+37	CL	1073
3360+45	3365+67	CL	1043
STAGE 4 - EVERETT ROAD			
3273+65	3280+20	EB	655
3273+65	3280+20	WB	655
3281+34	3287+43	EB	609
3281+34	3287+43	WB	609
STAGE 5 - RIVERWOODS ROAD			
3353+00	3359+37	EB	637
3353+00	3359+37	WB	637
3360+45	3365+67	EB	521
3360+45	3365+67	WB	521
STAGE 5 - EVERETT ROAD			
3273+65	3280+20	EB	655
3273+65	3280+20	WB	655
3281+34	3287+43	EB	609
3281+34	3287+43	WB	609
SUBTOTAL			20849
PROJECT TOTAL			20849

REVISIONS / REMARKS		DATE	BY	DESIGNED BY:	JRM
NO.	DESCRIPTION	/ /		CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010

HDR
38 N LaSalle Street, Suite 3220
Chicago, IL 60602
312-443-4900
HDR Engineering, Inc.

LakeCounty
Division of Transportation

SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	13	107

63415