

68 SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING LINE 4 INCH (78000200)				
FROM	TO	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD				
3354+61.00	3356+45.00	4	184.0	736
3362+95.00	3364+49.00	4	154.0	616
			SUBTOTAL	1352
EVERETT ROAD				
3276+07.00	3277+70.00	4	163.0	652
3284+10.00	3286+05.00	4	195.0	780
			SUBTOTAL	1432
			PROJECT TOTAL	2784

69 SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING LINE 5 INCH (78000200)			
LOCATION	# OF LINES	FOOT EACH	FOOT
INTERSECTION			
NW CORNER	1	188.0	188
NE CORNER	1	225.0	225
SW CORNER	1	216.0	216
SE CORNER	1	194.0	194
		SUBTOTAL	823
		PROJECT TOTAL	823

70 SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING LINE 6 INCH (78000200)				
FROM	TO	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD				
3353+00.00	3354+24.00	1	124.0	124
3354+24.00	3356+14.00	24	2.0	48
			SUBTOTAL	172
			PROJECT TOTAL	172

71 SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING LINE 8 INCH (78000500)				
FROM	TO	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD				
3356+45.00	3359+10.00	1	564.0	564
3359+09.00	3353+25.00	5	2.0	10
3360+44.00	3360+59.00	5	2.0	10
3361+43.00	3362+95.00	1	514.0	514
			SUBTOTAL	1098
EVERETT ROAD				
3277+70.00	3280+18.00	1	528.0	528
3280+14.00	3280+27.00	5	2.0	10
3281+45.00	3281+64.00	5	2.0	10
3281+64.00	3284+10.00	1	523.0	523
			SUBTOTAL	1071
			PROJECT TOTAL	2169

72 SCHEDULE OF THERMOPLASTIC PAVEMENT MARKING LINE 12 INCH (78000600)			
STATION	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD			
3354+79.00	1	1.0	1
3354+98.00	1	3.0	3
3355+18.00	1	5.0	5
3355+37.00	1	7.0	7
3355+56.00	1	9.0	9
3355+76.00	1	10.0	10
3355+95.00	1	12.0	12
3356+14.00	1	14.0	14
3356+34.00	1	15.0	15
3363+00.00	1	9.0	9
3363+20.00	1	8.0	8
3363+40.00	1	7.0	7
3363+60.00	1	5.0	5
3363+78.00	1	4.0	4
3363+98.00	1	3.0	3
3364+18.00	1	2.0	2
3364+38.00	1	1.0	1
		SUBTOTAL	115
EVERETT ROAD			
3276+21.00	1	1.0	1
3276+41.00	1	2.0	2
3276+61.00	1	3.0	3
3276+80.00	1	4.0	4
3277+00.00	1	6.0	6
3277+19.00	1	8.0	8
3277+38.00	1	9.0	9
3277+58.00	1	11.0	11
3284+21.00	1	12.0	12
3284+40.00	1	10.0	10
3284+60.00	1	9.0	9
3284+79.00	1	8.0	8
3284+99.00	1	7.0	7
3285+18.00	1	5.0	5
3285+38.00	1	4.0	4
3285+57.00	1	3.0	3
3285+76.00	1	2.0	2
3285+96.00	1	1.0	1
		SUBTOTAL	105
		PROJECT TOTAL	220

REVISIONS / REMARKS					
NO.	DESCRIPTION	DATE	BY	DESIGNED BY:	JRM
		/ /		CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010

**HDR** 30 N LaSalle Street, Suite 3220  
Chicago, IL 60602  
312-443-4900  
HDR Engineering, Inc.



SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	15	107

63415

FILE NAME: