

73 SCHEDULE OF PAINT PAVEMENT MARKING LINE 4 INCH (78001110)

FROM	TO	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD				
3353+00.00	3354+34.00	2	134.0	268
3364+49.00	86+08.00	2	294.0	588
			SUBTOTAL	856
EVERETT ROAD				
100+41.00	3276+07.00	2	669.0	1338
3286+51.00	9+80.00	2	415.0	830
			SUBTOTAL	2168
			PROJECT TOTAL	3024

76 SCHEDULE OF CURB CUT (X0322494)

STRUCTURE #	STATION	LOCATION	LENGTH (FOOT)
EVERETT ROAD			
1	3279+66.29	23.98, LT	8.50
2	3279+68.69	24.04, RT	8.50
35	3282+23.59	21.88, RT	8.50
36	3282+31.62	20.00, LT	8.50
RIVERWOODS ROAD			
8	3361+07.27	20.08, LT	8.50
9	3361+06.63	26.06, RT	8.50
31	3361+99.85	19.73, LT	8.50
32	3362+30.70	19.21, RT	8.50
33	3358+51.66	23.39, LT	8.50
34	3358+54.52	20.03, RT	8.50
		PROJECT TOTAL	85

74 SCHEDULE OF PAINT PAVEMENT MARKING LINE 5 INCH (780011120)

FROM	TO	# OF LINES	FOOT EACH	FOOT
RIVERWOODS ROAD				
3353+00.00	3359+11.00	1	511.0	511
3353+00.00	3359+53.00	1	553.0	553
3361+16.00	86+08.00	1	627.0	627
3361+54.00	86+08.00	1	588.0	588
			SUBTOTAL	2279
EVERETT ROAD				
100+41.00	3279+42.00	1	1003	1003
100+41.00	3279+52.00	1	1017	1017
3282+25.00	9+80.01	1	839	839
3282+52.00	9+80.00	1	817.0	817
			SUBTOTAL	3676
			PROJECT TOTAL	5955

77 SCHEDULE OF TEMPORARY PAVEMENT (X0712400)

FROM	TO	AREA (SQ FT)	AREA (SQ YD)
IRRIGATION			
		1966	218
STAGE 1			
EVERETT ROAD			
3269+97	3280+52	14512	1612
3282+00	3290+32	16417	1824
RIVERWOODS ROAD			
3355+70	3359+43	6392	710
3359+74	3367+24	13327	1481
		STAGE 1 SUBTOTAL	5628
STAGE 2			
EVERETT ROAD			
3277+71	3279+79	2699	300
3279+87	3280+14	589	65
3280+36	3280+67	1449	161
3281+65	3281+92	448	50
3282+00	3284+09	2313	257
		STAGE 2 SUBTOTAL	833
STAGE 3			
RIVERWOODS ROAD			
3356+46	3356+74	2269	252
3358+82	3358+09	432	48
3360+59	3360+86	500	56
3360+93	3360+94	1798	200
		STAGE 3 SUBTOTAL	555
		PROJECT TOTAL	7235

75 SCHEDULE OF RAISED REFLECTIVE PAVEMENT MARKER (78100100)

FROM	TO	EACH
RIVERWOODS ROAD		
3353+00.00	3358+98.00	36
3360+69.00	3365+09.00	24
		SUBTOTAL
EVERETT ROAD		
3275+66.00	3280+07.00	24
3281+74.00	3286+15.00	24
		SUBTOTAL
INTERSECTION		
		8
		SUBTOTAL
		PROJECT TOTAL

REVISIONS / REMARKS					
NO.	DESCRIPTION	DATE	BY	DESIGNED BY:	JRM
		/ /		CHECKED BY:	MPK/JLC
		/ /		DATE:	1/22/2010

HDR 30 N LaSalle Street, Suite 3220
Chicago, IL 60602
312-443-4900
HDR Engineering, Inc.

 **LakeCounty**
Division of Transportation

SCHEDULE OF QUANTITIES

ROUTE	SECTION	SECTION NUMBER	SHEET	SHEETS
CH	136	04-00136-06-CH	16	107

63415

FILE NAME: