REMOVAL AND ADJUSTMENTS SCHEDULE

SHEET	STATION	TO	STATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	FRAMES AND LIDS TO BE ADJUSTED	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH; THREE FEET OR LESS IN WIDTH	RELOCATE EXISTING CONCRETE PARKING BUMPER	RELOCATE WATER METER AND VALVE WITH CAGED ENCLOSURE, COMPLETE	RELOCATE FLOOR DRAIN AND DRYWELL, COMPLETE	RELOCATE WATER FOUNTAIN, COMPLETE	REMOVE EXISTING BARRIER SWING GATE	REMOVE EXISTING BENCH, RELOCATE OR SALVAGE	RELOCATE EXISTING FITNESS STATION	RELOCATE EXISTING PICNIC AREA
				UNIT	UNIT	SQ YD	FOOT	SQ FT	EACH	EACH	SQ YD	EACH	EACH	EACH	EACH	EACH	EACH	EA	EA
				20100110	20100210	44000100	44000500	44000600	56500600	60300305	********	********	********	********	********	********	********	********	********
REM_01	50+00	TO	55+70	6	-	43	48	698	1	-	16	1	1	1	1	-	5	-	-
REM_02	55+70	TO	61+50	38	-	490	14	-	-	2	5	-	-	-	-	-	3	-	-
REM_03	61+50	TO	67+50	10	-	690	14	-	-	-	5	-	-	-	-	-	10	-	-
REM_04	67+50	TO	73+50	19	-	610	101	316	-	1	34	24	-	-	-	1	-	-	-
REM_05	73+50	TO	80+00	34	20	970	26	-	-	2	9	35	-	-	-	-	-	-	-
REM_06	80+00	TO	86+00	12	38	540	14	-	-	-	5	-	-	-	-	-	3	-	-
REM_07	86+00	TO	92+00	-	-	570	6	-	-	-	2	-	-	-	-	-	6	-	-
REM_08	92+00	TO	97+00	-	16	330	14	-	-	-	-	-	-	-	-	-	-	-	-
REM_09	97+00	TO	102+00	-	-	560	-	-	-	-	-	-	-	-	-	-	1	1	1
REM_10	102+00	TO	106+83.41	16	-	500	-	-	-	-	-	-	-	-	-	-	1	-	-
			TOTALS	135	74	5303	237	1014	1	5	76	60	1	1	1	1	29	1	1

PATH SCHEDULE

SHEET	STATION	TO	STATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION**	AGGREGATE BASE COURSE, TYPE B 6"	AGGREGATE BASE COURSE, TYPE B 8"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	DETECTABLE WARNINGS	CONCRETE CURB, TYPE B	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V 12	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (HAND METHOD)	CRUSHED NATURAL STONE PATH SURFACE, 4"
				SQ YD	SQ YD	SQ YD	GALLON	TON	TON	SQ YD	SQ FT	SQ FT	FOOT	FOOT	TON	SQ YD
				21001000	35101800	35102000	40300100	40603080	40603310	42001300	42400200	42400800	60600605	XX104800	********	********
PLAN_01	50+00	TO	55+70	945	-	945	324	102.1	68.1	181	1532	26	-	48	2.7	-
PLAN_02	55+70	TO	61+50	1402	494	908	312	98.1	65.4	112	977	28	-	14	0.8	423
PLAN_03	61+50	TO	67+50	1552	618	934	321	100.9	67.3	78	666	24	-	14	0.8	529
PLAN_04	67+50	TO	73+50	935	91	844	290	91.2	60.8	179	1361	140	45	101	5.7	78
PLAN_05	73+50	TO	80+00	1041	189	852	293	92.1	61.4	56	447	24	-	26	1.5	162
PLAN_06	80+00	TO	86+00	985	51	934	321	100.9	67.3	83	716	28	-	14	0.8	43
PLAN_07	86+00	TO	92+00	1116	182	934	321	100.9	67.3	58	504	12	-	6	0.3	156
PLAN_08	92+00	TO	97+00	1089	311	778	267	84.1	56.1	32	256	12	-	14	0.8	266
PLAN_09	97+00	TO	102+00	720	-	720	247	77.8	51.9	-	0	-	-	-	-	-
PLAN_10	102+00	TO	106+83.41	1112	285	827	284	89.4	59.6	-	18	-	-	-	-	244
			TOTALS	10897	2221	8676	2980	937.5	625.2	779	6477	294	45	237	13.3	1901

12/01/2009
\\uschgl\p207\p60099576\p60099576\1900_cad\90_drawings\sheet\005_D933807_sht_sch_qty_01.dgn

AECOM

USER NAME = czosnykab	DESIGNED - BMC	REVISED -
	DRAWN - LM	REVISED -
PLOT SCALE =	CHECKED - SLW	REVISED -
PLOT DATE = 12/01/2009	DATE - 12/01/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

C-91-338-07

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00246-00-BT	COOK	81	5
ITEP NO. 102121		CONTRACT NO. 63423		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		