EARTHWORK SCHEDULE

SHEET	STATION	TO	STATION	EARTH EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE**	EMBANKMENT	EARTHWORK BALANCE
				CU YD	CU YD	CU YD	CU YD	CU YD
				20200100	20201200	-	-	-
REM_01	50+00	TO	55+70	312	32	266	69	-197
REM_02	55+70	TO	61+50	380	38	323	151	-172
REM_03	61+50	TO	67+50	378	38	322	173	-149
REM_04	67+50	TO	73+50	110	12	94	41	-53
REM_05	73+50	TO	80+00	147	15	126	137	11
REM_06	80+00	TO	86+00	307	31	262	187	-75
REM_07	86+00	TO	92+00	311	32	264	177	-87
REM_08	92+00	TO	97+00	303	31	258	127	-131
REM_09	97+00	TO	102+00	146	15	124	117	-7
REM_10	102+00	TO	106+83.41	216	22	184	72	-112
			TOTALS	2610	266	2223	1252	-971

** A 15% SHRINKAGE FACTOR HAS BEEN APPLIED

EROSION CONTROL SCHEDULE

SHEET	STATION	TO	STATION	MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
				ACRE	SQ YD	POUND	FOOT	EACH
				25100115	25100630	28000250	28000400	28000510
EC_01	50+00	TO	64+50	1.82	8761	2184	5000	
EC_02	64+50	TO	79+00					1
EC_03	79+00	TO	93+00	1.52	7330	1824		
EC_04	93+00	TO	106+83					
			TOTALS	3.3	16091	4008	5000	1

PAVEMENT MARKING SCHEDULE

SHEET	STATION	TO	STATION	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"
				FOOT	FOOT	FOOT	FOOT
				78000200	7800400	7800600	78000650
PLAN_01	50+00	TO	55+70	143	-	-	6
PLAN_02	55+70	TO	61+50	145	-	-	-
PLAN_03	61+50	TO	67+50	150	-	-	-
PLAN_04	67+50	TO	73+50	132	125	192	12
PLAN_05	73+50	TO	80+00	163	-	-	-
PLAN_06	80+00	TO	86+00	150	-	-	-
PLAN_07	86+00	TO	92+00	150	-	-	-
PLAN_08	92+00	TO	97+00	125	-	-	-
PLAN_09	97+00	TO	102+00	116	-	-	12
PLAN_10	102+00	TO	106+83.41	121	-	-	-
			TOTALS	1394	125	192	30

SIGNING SCHEDULE

SHEET	STATION	TO	STATION	SIGN PANEL - TYPE 1	METAL POST - TYPE A	METAL POST - TYPE B
				SQ FT	FOOT	FOOT
				72000100	72900100	72900200
PLAN_01	50+00	TO	55+70	8.9	36	
PLAN_02	55+70	TO	61+50	-	-	-
PLAN_03	61+50	TO	67+50	-	-	-
PLAN_04	67+50	TO	73+50	22	50	26
PLAN_05	73+50	TO	80+00	-	-	-
PLAN_06	80+00	TO	86+00	-	-	-
PLAN_07	86+00	TO	92+00	-	-	-
PLAN_08	92+00	TO	97+00	-	-	-
PLAN_09	97+00	TO	102+00	2.5	12	
PLAN_10	102+00	TO	106+83.41	9.2	36	-
			TOTALS	43	134	26

SITE FURNISHINGS SCHEDULE

SHEET	STATION	TO	STATION	BICYCLE RACKS	BENCH - RECYCLED PLASTIC	TRASH AND RECYCLING RECEPTACLES, FURNISH AND INSTALL
				EA	EA	EA
				XX001011	XX006092	********
PLAN_01	50+00	TO	55+70	12	5	2
PLAN_02	55+70	TO	61+50	10	3	2
PLAN_03	61+50	TO	67+50	-	10	1
PLAN_04	67+50	TO	73+50	10	-	1
PLAN_05	73+50	TO	80+00	8	-	1
PLAN_06	80+00	TO	86+00	2	4	1
PLAN_07	86+00	TO	92+00	8	6	1
PLAN_08	92+00	TO	97+00	10	-	2
PLAN_09	97+00	TO	102+00	-	-	-
PLAN_10	102+00	TO	106+83.41	-	-	1
			TOTALS	60	28	12

12/01/2009
\\uschgo1fp201\p60039576\p60099576\900_cad\90_drawings\sheet\006_09133807-sht-sch-qty_02.dgn

AECOM

USER NAME = czosnykab	DESIGNED - BMC	REVISED -
	DRAWN - LM	REVISED -
PLOT SCALE =	CHECKED - SLW	REVISED -
PLOT DATE = 12/01/2009	DATE - 12/01/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

C-91-338-07

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00246-00-BT	COOK	81	6
ITEP NO. 102121		CONTRACT NO. 63423		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		