

PAY ITEM CODE NO.	SI	SP	PAY ITEM DESCRIPTION	UNIT	TOTAL	ITEP			IDOT		NON PARTICPATING			
						LANDSCAPING (80/20)	LIGHTING (80/20)	LIGHTING (50/50)	ROADWAY	TRAFFIC SIGNALS	MAINTENANCE	LANDSCAPING	ROADWAY	LIGHTING
						Y003	YO30-1E	YO30-1E	I000	Y031-1F	Y007			
20100110			TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	40	40								
20101000			TEMPORARY FENCE	FOOT	39	39								
20101200	X		TREE ROOT PRUNING	EACH	17	5						12		
20101350	X		TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	17	5						12		
20800150			TRENCH BACKFILL	CU YD	3,694	2808			762				124	
21101615	X		TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,586							2586		
21101810	X		COMPOST FURNISH AND PLACE, 3"	SQ YD	456	351						105		
25000400	X		NITROGEN FERTILIZER NUTRIENT	POUND	12	9.60						2.40		
25000500	X		PHOPHORUS FERTILIZER NUTRIENT	POUND	4	3.20						0.80		
25000600	X		POTASSIUM FERILIZER NUTRIENT	POUND	8	6.30						1.70		
25200110	X		SODDING, SALT TOLERANT	SQ YD	2,716							2716		
25400100	X		PERENNIAL PLANTS	UNIT	16	12.79						3.21		
28000400			PERIMETER EROSION BARRIER	FOOT	117	117								
28000510			INLET FILTERS	EACH	133	65						68		
28200200			FILTER FABRIC	SQ YD	1,742	1633						109		
31101000			SUB-BASE GRANULAR MATERIAL, TYPE B	TON	10,643	6671			2854			792	326	
35200600			EARTH EXCAVATION	CU YD	9,490	6356.0			2353			490.0	291	
35300500			P.C.C. BASE COURSE 10"	SQ YD	1,138	775			363					
35400500			PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	82	82								
40300200			BITUMINOUS MATERIALS (PRIME COAT)	TON	90.2				84.90				5.30	
40600300			AGGREGATE (PRIME COAT)	TON	111				104.00				7.00	
40600525			LEVELING BINDER (HAND METHOD), N50	TON	60				60.00					
40600895			CONSTRUCTING TEST STRIP	EACH	2				2					
40600982			HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	786				114				672	
40600990			TEMPORARY RAMP	SQ YD	3,020				3020					
40603240			POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	6,164				5797.20				366.80	
40603595			POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4,315				4058.50				256.50	
42001300			PROTECTIVE COAT	SQ YD	21,429	18148.0							3281	
42300400			PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,249	1249								
42400430	*		PCC SIDEWALK 5 INCH, SPECIAL	SQ FT	131,570	110631							20939	
42400800			DETECTABLE WARNINGS	SQ FT	1,028	1028								
44000100			PAVEMENT REMOVAL	SQ YD	5,779	4797			363				619	
44000198	*		HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	41,766				39777				1989	
44000200			DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,289	1281							8	
44000500			COMBINATION CURB AND GUTTER REMOVAL	FOOT	17,385	3814			12011				1560	
44000600			SIDEWALK REMOVAL	SQ FT	106,149	91411							14738	
44002000	*		CONCRETE CURB REMOVAL	FOOT	45	11							34	
44201325			CLASS C PATCHES, TYPE I, 8 INCH	SQ YD	7								7	
44201329			CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	11								11	
44201737			CLASS D PATCHES TYPE I, 8 INCH	SQ YD	4	4								
44201741			CLASS D PATCHES TYPE II, 8 INCH	SQ YD	44	38							6	
44201745			CLASS D PATCHES TYPE III, 8 INCH	SQ YD	237	237								
44201747			CLASS D PATCHES TYPE IV, 8 INCH	SQ YD	577	531							46	
44300100			AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	43,074				43074					
50800305	*		WELDED WIRE FABRIC 6X6	SQ YD	6,231	4142							2089	
55039700	*		STORM SEWERS TO BE CLEANED	FOOT	14357.00						14357.00			
56400100	X		FIRE HYDRANTS TO BE MOVED	EACH	1	1								
56500600	*		DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	172	158			8				6	
60107600			PIPE UNDERDRAINS 4"	FOOT	959	828						131		
60200105			CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	95	54			38				3	
60218400			MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	61	40			16				5	
60221100			MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	4			5					
60250200			CATCH BASINS TO BE ADJUSTED	EACH	80				55				25	
60500040			REMOVING MANHOLES	EACH	9	9								
60500050			REMOVING CATCH BASINS	EACH	15	15								
60600605			CONCRETE CURB, TYPE B	FOOT	200	200								
60611600	*		COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	18,961	5199			12297				1465	
67000400			ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15				15					
67100100			MOBILIZATION	L SUM	1	0.61			0.29				0.10	
70101800	*		TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1				1.00					
70300220			TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67,922				67922					
70300240			TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7,579	7579								
70300260			TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,519				1519					
70300280			TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,153				3153					
72000100	X		SIGN PANEL - TYPE 1	SQ FT	256	256								
72400100	X		REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	76	76								
72400310	X		REMOVE SIGN PANEL - TYPE 1	SQ FT	398	398								
72400710	X		RELOCATE SIGN PANEL - TYPE 1	SQ FT	1,086	1086								
78000100	X		THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,555				1555					
78000200	X		THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,304				14304					
78000400	X		THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,382	3472			1910					
78000600	X		THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	298				298					
78000650	X		THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	925				925					
78100100	X		RAISED REFLECTIVE PAVEMENT MARKER	EACH	402				402					
78300200	X		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	402				402					
80400100	X		ELECTRIC SERVICE INSTALLATION	EACH	6		6							

FILE NAME = DIRTE38-sh-50001.dgn	USER NAME = IDOT	DESIGNED - BB	REVISED -
		DRAWN - TM	REVISED -
PLOT SCALE = 20.0000 "/>			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: 1" = 20'	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE. 347	SECTION 09-00248-00-RS	COUNTY COOK	TOTAL SHEETS 274	SHEET NO. 3
CONTRACT NO. 63432				
ILLINOIS FED. AID PROJECT				