


SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADSIDE IMPROVEMENTS	
				80% FED	20% VILLAGE SFTY-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	9	9	
20101200	TREE ROOT PRUNING	EACH	4	4	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,062	1,062	
20400800	FURNISHED EXCAVATION	CU YD	101	101	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	2.2	2.2	
28000400	PERIMETER EROSION BARRIER	FOOT	520	520	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28000510	INLET FILTERS	EACH	13	13	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500	500	
42001300	PROTECTIVE COAT	SQ YD	3,012	3,012	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	54	54	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	25,826	25,826	
42400800	DETECTABLE WARNINGS	SQ FT	64	64	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	945	945	
44000300	CURB REMOVAL	FOOT	382	382	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	194	194	
44000600	SIDEWALK REMOVAL	SQ FT	273	273	
50901115	STEEL RAILING (SPECIAL)	FOOT	265	265	
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	4	4	
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1	1	
60600605	CONCRETE CURB, TYPE B	FOOT	382	382	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	170	170	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	24	24	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	353	353	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	69	69	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	138	138	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4	
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	945	945	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	7	7	
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	3	3	
Z0066700	STABILIZED DRIVEWAYS 10"	SQ YD	512	512	

LEGEND  
 -DENOTES SPECIALTY ITEM

**JJB** JAMES J. BENES & ASSOCIATES, INC.  
 950 Warrenville Road, Suite 101, Lisle, Illinois 60532  
 Tel. (630) 719-7570 • Fax (630) 719-7589

FILE NAME =	USER NAME =	DESIGNED -- BDH	REVISED --	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES F.A.P. ROUTE 351 (IL ROUTE 7)</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -- SMP	REVISED --		351	09-00063-00-SW	WILL	41	3			
		CHECKED -- BDH	REVISED --		SCALE: NONE SHEET NO. 3 OF 41 SHEETS STA. _____ TO STA. _____			CONTRACT NO. 63438				
		DATE -- 11-06-09	REVISED --		ILLINOIS FED. AID PROJECT							