

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1800	06-00008-00-ST	WILL	73	2
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	CMM-0001 (973)	

CONTRACT #63440

SUMMARY OF QUANTITIES					PAVEMENT
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONST. TYPE CODE
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	60	Y047
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	
	20101100	TREE TRUNK PROTECTION	EACH	19	
	20200100	EARTH EXCAVATION	CU YD	17665	17665
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	200	200
	20800150	TRENCH BACKFILL	CU YD	26	26
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	48581	48581
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200	200
	25000312	SEEDING, CLASS 4A	ACRE	9.1	9.1
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	60	60
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	60	60
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	60	60
	25100115	MULCH, METHOD 2	ACRE	9.1	9.1
	25100630	EROSION CONTROL BLANKET	SQ YD	13234	13234
	25200110	SODDING, SALT TOLERANT	SQ YD	4467	4467
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900
	28000305	TEMPORARY DITCH CHECKS	FOOT	544	544
	28000400	PERIMETER EROSION BARRIER	FOOT	16900	16900
	28000500	INLET AND PIPE PROTECTION	EACH	13	13
	28100105	STONE RIPRAP, CLASS A3	SQ YD	338	338
	28100109	STONE RIPRAP, CLASS A5	SQ YD	304	304
	28100111	STONE RIPRAP, CLASS A6	SQ YD	263	263
	28200200	FILTER FABRIC	SQ YD	653	653
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	44275	44275
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7825	7825
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2201	2201
	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	564	564
	42400800	DETECTABLE WARNINGS	SQ FT	400	400
	44000600	SIDEWALK REMOVAL	SQ FT	1208	1208
	44002300	CURB REMOVAL (PARTIAL)	FOOT	225	225
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	83	83
	54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	6	6
	54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	2	2
	54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	2	2
	54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH	2	2
	54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	2	2
	54010602	PRECAST CONCRETE BOX CULVERT 6' X 2'	FOOT	52	52
	54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	140	140
	54010804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	120	120
	54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'	FOOT	144	144
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1
	54213867	STEEL END SECTIONS 12"	EACH	10	10
	54213870	STEEL END SECTIONS 15"	EACH	4	4
	54213873	STEEL END SECTIONS 18"	EACH	2	2
	54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2
	54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**HOMER GLEN GMAQ COMMUNITY BIKE TRAIL AND EAST EXTENSION**

**SUMMARY OF QUANTITIES**

SCALE: VERT. N/A  
 HORIZ. N/A  
 DATE FEBRUARY 2, 2010

DRAWN BY JUB  
 CHECKED BY BDB