

SI	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED, 20% LOCAL	
						ROADWAY SFTY-3J	STRUCTURAL X071-2A
	*	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	126		126
		25000300	SEEDING, CLASS 3	ACRE	0.25		0.25
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23		23
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23		23
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23		23
		25100630	EROSION CONTROL BLANKET	SQ YD	191		191
		28000400	PERIMETER EROSION BARRIER	FOOT	683		683
		28100107	STONE RIPRAP, CLASS A4	SQ YD	375		375
		28200200	FILTER FABRIC	SQ YD	375		375
		40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3		3
		42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44		44
	*	44000700	APPROACH SLAB REMOVAL	SQ YD	240		240
		50102400	CONCRETE REMOVAL	CU YD	39.9		39.9
		50104650	SLOPE WALL REMOVAL	SQ YD	375		375
	*	50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1		1
		50157300	PROTECTIVE SHIELD	SQ YD	2334		2334
		50200100	STRUCTURE EXCAVATION	CU YD	156		156
		50300225	CONCRETE STRUCTURES	CU YD	69.4		69.4
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	900.0		900.0
		50300260	BRIDGE DECK GROOVING	SQ YD	2224		2224
		50300300	PROTECTIVE COAT	SQ YD	2961		2961
		50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
		50500505	STUD SHEAR CONNECTORS	EACH	2580		2580
	*	50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	30		30
	*	50501110	STRUCTURAL STEEL REMOVAL	POUND	3790		3790
	+	50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1		1
	+	* 50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1		1
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	211,470		211,470
		50800515	BAR SPLICERS	EACH	62		62
		51500100	NAME PLATES	EACH	1		1
		52000110	PREFORMED JOINT STRIP SEAL	FOOT	96.0		96.0
		52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	10		10
		52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10		10
		52100520	ANCHOR BOLTS, 1"	EACH	40		40

SP = SPECIAL PROVISION
SI = SPECIALTY ITEMS

△ Y080

SI	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED, 20% LOCAL	
						ROADWAY SFTY-3J	STRUCTURAL X071-2A
		52100530	ANCHOR BOLTS, 1 1/4"	EACH	20		20
		58700300	CONCRETE SEALER	SQ FT	755		755
		59000200	EPOXY CRACK INJECTION	FOOT	198		198
		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	65		65
	*	60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	104		104
	+	63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	150	150	
	+	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
	+	* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
	+	* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1	
		63200310	GUARDRAIL REMOVAL	FOOT	427	427	
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7		7
		67000600	ENGINEER'S FIELD LABORATORY	CAL MO	7		7
		67100100	MOBILIZATION	L SUM	1		1
	*	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1		1
		70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14		14
	+	72000100	SIGN PANEL - TYPE 1	SQ FT	8		8
	+	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	8		8
	+	72900110	METAL POST - TYPE A	EACH	1		1
	+	* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	58		58
	+	* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,106		2,106
	+	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	20		20
	+	* 78200405	GUARDRAIL MARKERS	EACH	13		13
	*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	20		20
	+	* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
	*	X0323080	DRAINAGE SCUPPERS, DS-12	EACH	8		8
	*	X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	35		35
	*	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	44		44
	*	X0326345	TURBIDITY BARRIER	FOOT	98		98
	*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
	*	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
	*	△ Z0076600	TRAINEES	HOUR	1000		1000

FILE NAME = ...Neav1\DI-63442-shr-500.dgn
PLOT DATE = 2/26/2018 11:01:07 AM

DESIGNED - JRM
DRAWN - JRM
CHECKED - JAS
DATE - 12/1/09

REVISED -
REVISED -
REVISED -
REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	04-00090-07-BR	WILL	57	3
CONTRACT NO. 63442				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				