

				URBAN	ACHSIP 1000-1A	ACHSIP Y031-1F
	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	90% FED / 10% STATE ROADWAY	90 % FED / 5% STATE / 5% TOWNSHIP TRAFFIC SIGNALS
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,079	1,079	
	40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,585	1,585	
	42001200	PAVEMENT FABRIC	SQ YD	359	359	
	44000100	PAVEMENT REMOVAL	SQ YD	111	111	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	665	665	
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	2,404	2,404	
	44004250	PAVED SHOULDER REMOVAL	SQ YD	2,824	2,824	
	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	744	744	
	44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	20	20	
	44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	339	339	
	44213200	SAW CUTS	FOOT	5,457	5,457	
	48203019	HOT-MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	7,003	7,003	
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	169	169	
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	12	12	
	60107600	PIPE UNDERDRAINS 4"	FOOT	5,940	5,940	
	60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	398	398	
	64200105	SHOULDER RUMBLE STRIP	FOOT	6,916	6,916	
	66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	
	67100100	MOBILIZATION	L SUM	1	1	
	70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	2	2	

\* SPECIALTY ITEMS

: ) NON PARTICIPATING 100% STATE

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>US BR 20 SUMMARY OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\pw\dot\dssdd\dms50890\0205704-sh1-S00.dgn		DRAWN -	REVISED -		517	(1-2)M & TS	BOONE	74	4				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -						CONTRACT NO. 64A09				
PLOT DATE = Wed Dec 30 11:47:04 2009		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		