

SCHEDULE OF QUANTITIES

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION				
	<u>US 20 BR</u>				
11.1	Sta	265 + 21 - 265 + 71		LT (25' x 4') for Shoulder	
11.1	Sta	265 + 21 - 265 + 71		RT (25' x 4') for Shoulder	
28.9	Sta	301 + 80 - 302 + 30		LT (25' x 10.4') for Shoulder	
19.4	Sta	301 + 80 - 302 + 30		RT (25' x 7') for Shoulder	
<u>70.5</u>	TOTAL				

40600985 PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION				
	<u>US 20 BR</u>				
161.1	Sta	265 + 21 - 265 + 71		(25' x 58') for Pavement	
116.7	Sta	301 + 80 - 302 + 30		(25' x 42') for Pavement	
<u>277.8</u>	TOTAL				

40600990 TEMPORARY RAMP

SQ YD	LOCATION				
	<u>US 20 BR</u>				
62.3	Sta	265 + 21 (66' x 8.5')			
55.7	Sta	302 + 30 (59' x 8.5')			
94.4	N. McKinley Ave. (100' x 8.5')				
102.0	S. McKinley Ave. (108' x 8.5')				
<u>314.4</u>	TOTAL				

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION				
	<u>US 20 BR</u>				
14.0	Sta	278 + 00 - 280 + 81		RT Shoulder - Stage 1	
60.5	Sta	284 + 07 - 296 + 22		RT Shoulder - Stage 1	
<u>74.5</u>	TOTAL				

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION				
	<u>US 20 BR</u>				
17.6	Sta	280 + 73 - 280 + 81		RT	
67.6	Sta	282 + 48 - 283 + 11		LT	
24.9	Sta	283 + 83 - 284 + 07		RT	
<u>110.1</u>	TOTAL				

44000157 HOT-MIX ASPHALT SURFACE REMOVAL, 2"

SQ YD	LOCATION				
	<u>US 20 BR</u>				
125.0	Sta	278 + 00 - 280 + 81		RT Shoulder - Stage 1	
539.9	Sta	284 + 07 - 296 + 22		RT Shoulder - Stage 1	
<u>664.9</u>	TOTAL				

44000159 HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"

SQ YD	LOCATION				
	<u>US 20 BR</u>				
237.6	Sta	280 + 26 - 280 + 76		50' Taper w/ Shoulders	
1,934.9	Sta	280 + 76 - 283 + 82		Mainline w/ Returns	
230.8	Sta	283 + 82 - 284 + 32		50' Taper w/ Shoulders	
<u>2,403.3</u>	TOTAL				

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION				
	<u>US 20 BR</u>				
676.1	Sta	265 + 21 - 280 + 07		LT	
695.2	Sta	265 + 21 - 280 + 73		RT	
598.7	Sta	283 + 11 - 296 + 22		LT	
539.9	Sta	284 + 07 - 296 + 22		RT	
313.5	Sta	296 + 22 - 299 + 00		LT	
<u>2,823.4</u>	TOTAL				