

SCHEDULE OF QUANTITIES

70300660 TEMPORARY PAINT PAVEMENT MARKING LINE 24"

CAL MO LOCATION

US 20 BR

2 As Directed by the Resident and Operations

(2 Signs for 1 Month Each)

2 TOTAL

FOOT LOCATION

US 20 BR

200 As Needed & Directed by the Resident

200 TOTAL

70300100 SHORT-TERM PAVEMENT MARKING

FOOT LOCATION

US 20 BR

*3 Applications - Prime, LB (MM), & Surface

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT LOCATION

*Removal of Short-Term on Surface Only

FOOT	LOCATION	DESCRIPTION
192	Sta 265 + 21 - 280 + 75	1 Stripe - 4' @ 100' o.c. (White Shoulder Diagonal - LT)
144	Sta 265 + 21 - 277 + 00	1 Stripe - 4' @ 100' o.c. (White Shoulder Diagonal - RT)
192	Sta 287 + 00 - 302 + 30	1 Stripe - 4' @ 100' o.c. (White Shoulder Diagonal - LT)
240	Sta 283 + 00 - 302 + 30	1 Stripe - 4' @ 100' o.c. (White Shoulder Diagonal - RT)
1,536	Sta 265 + 21 - 277 + 78	4 Stripes - 4' @ 40' o.c. (Yellow Median)
216	Sta 277 + 78 - 281 + 33	2 Stripes - 4' @ 40' o.c. (Double Yellow)
216	Sta 282 + 69 - 286 + 21	2 Stripes - 4' @ 40' o.c. (Double Yellow)
1,968	Sta 286 + 21 - 302 + 30	4 Stripes - 4' @ 40' o.c. (Yellow Median)
210	Sta 277 + 83 - 281 + 33	2 Stripes - 4' @ 40' o.c. (White - LT Turn Lane)
192	Sta 278 + 30 - 281 + 31	2 Stripes - 4' @ 40' o.c. (White - RT Turn Lane)
210	Sta 282 + 69 - 286 + 19	2 Stripes - 4' @ 40' o.c. (White - LT Turn Lane)
192	Sta 282 + 70 - 285 + 54	2 Stripes - 4' @ 40' o.c. (White - RT Turn Lane)
5,508	TOTAL	

SQ FT	LOCATION	DESCRIPTION
21.3	Sta 265 + 21 - 280 + 75	1 Stripe - LT Shoulder Diagonal
16.0	Sta 265 + 21 - 277 + 00	1 Stripe - RT Shoulder Diagonal
21.3	Sta 287 + 00 - 302 + 30	1 Stripe - LT Shoulder Diagonal
26.7	Sta 283 + 00 - 302 + 30	1 Stripe - RT Shoulder Diagonal
170.7	Sta 265 + 21 - 277 + 78	4 Stripes - Yellow Median
24.0	Sta 277 + 78 - 281 + 33	2 Stripes - Double Yellow
24.0	Sta 282 + 69 - 286 + 21	2 Stripes - Double Yellow
218.7	Sta 286 + 21 - 302 + 30	4 Stripes - Yellow Median
23.3	Sta 277 + 83 - 281 + 33	2 Stripes - LT Turn Lane
21.3	Sta 278 + 30 - 281 + 31	2 Stripes - RT Turn Lane
23.3	Sta 282 + 69 - 286 + 19	2 Stripes - LT Turn Lane
21.3	Sta 282 + 70 - 285 + 54	2 Stripes - RT Turn Lane
612.0	TOTAL	

70300625 TEMPORARY PAINT PAVEMENT MARKING LINE 4"

FOOT LOCATION

US 20 BR

FOOT	LOCATION	DESCRIPTION
1,896	Sta 263 + 34 - 281 + 80	White EOP - LT (Stage 2)
4,950	Sta 256 + 00 - 280 + 75	Double Yellow (Stage 2)
2,605	Sta 256 + 00 - 281 + 50	White EOP - RT (Stage 2)
1,933	Sta 282 + 20 - 300 + 88	White EOP - LT (Stage 2)
3,565	Sta 283 + 05 - 300 + 88	Double Yellow (Stage 2)
1,883	Sta 282 + 40 - 300 + 88	White EOP - RT (Stage 2)
1,770	Sta 264 + 70 - 281 + 80	White EOP - LT (Stage 3)
3,876	Sta 261 + 42 - 280 + 80	Double Yellow (Stage 3)
2,083	Sta 261 + 42 - 281 + 75	White EOP - RT (Stage 3)
1,672	Sta 282 + 15 - 298 + 37	White EOP - LT (Stage 3)
3,093	Sta 282 + 90 - 298 + 37	Double Yellow (Stage 3)
1,677	Sta 282 + 25 - 298 + 37	White EOP - RT (Stage 3)
31,003	TOTAL	