

# SCHEDULE OF QUANTITIES

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

SQ FT	LOCATION		
	US 20 BR		
15.6	Sta	277 + 89	LT Turn Arrow
15.6	Sta	278 + 69	LT Turn Arrow
15.6	Sta	278 + 69	RT Turn Arrow
15.6	Sta	279 + 49	LT Turn Arrow
15.6	Sta	279 + 49	RT Turn Arrow
15.6	Sta	280 + 29	LT Turn Arrow
15.6	Sta	280 + 29	RT Turn Arrow
15.6	Sta	281 + 09	LT Turn Arrow
15.6	Sta	281 + 09	RT Turn Arrow
15.6	Sta	282 + 93	RT Turn Arrow
15.6	Sta	282 + 93	LT Turn Arrow
15.6	Sta	283 + 73	RT Turn Arrow
15.6	Sta	283 + 73	LT Turn Arrow
15.6	Sta	284 + 53	RT Turn Arrow
15.6	Sta	284 + 53	LT Turn Arrow
15.6	Sta	285 + 33	RT Turn Arrow
15.6	Sta	285 + 33	LT Turn Arrow
15.6	Sta	286 + 13	LT Turn Arrow
<b>280.8</b>	<b>TOTAL</b>		

FOOT	LOCATION			
	US 20 BR			
84	Sta	275 + 34	- 277 + 83	White Turkey Tracks (42 Stripes @ 2')
300	Sta	277 + 83	- 280 + 83	White - LT Turn Lane
302	Sta	278 + 30	- 281 + 31	White - RT Turn Lane
106	Sta	281 + 49	- 281 + 79	White Island - LT
99	Sta	282 + 18	- 282 + 47	White Island - RT
284	Sta	282 + 70	- 285 + 54	White - RT Turn Lane
300	Sta	283 + 19	- 286 + 19	White - LT Turn Lane
84	Sta	286 + 19	- 288 + 68	White Turkey Tracks (42 Stripes @ 2')
<b>1,559</b>	<b>TOTAL</b>			

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION			
	US 20 BR			
220	Sta	256 + 00	- 264 + 64	White Skip Dash - RT
130	Sta	263 + 34	- 268 + 55	White Skip Dash - LT
1,734	Sta	264 + 64	- 281 + 48	White EOP - LT
1,622	Sta	265 + 21	- 281 + 40	White EOP - RT
1,986	Sta	282 + 48	- 302 + 30	White EOP - LT
1,988	Sta	282 + 47	- 302 + 30	White EOP - RT
100	Sta	280 + 83	- 281 + 33	White Median (2 Lines)
100	Sta	282 + 69	- 283 + 19	White Median (2 Lines)
<b>7,880</b>	<b>White Sub-Total</b>			
1,520	Sta	261 + 42	- 265 + 21	Double Yellow Median (4 Lines)
5,032	Sta	265 + 21	- 277 + 78	Double Yellow Median (4 Lines)
710	Sta	277 + 78	- 281 + 33	Yellow Median (2 Lines)
710	Sta	282 + 69	- 286 + 21	Yellow Median (2 Lines)
6,440	Sta	286 + 21	- 302 + 30	Double Yellow Median (4 Lines)
<b>14,412</b>	<b>Yellow Sub-Total</b>			
<b>22,292</b>	<b>TOTAL</b>			

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION			
	US 20 BR			
351	Sta	261 + 42	- 265 + 21	Yellow Median Diagonals
820	Sta	265 + 21	- 281 + 33	Yellow Median Diagonals
1,056	Sta	282 + 69	- 302 + 30	Yellow Median Diagonals
<b>2,227</b>	<b>Yellow Sub-Total</b>			
12	Sta	280 + 83	- 281 + 33	White Median Diagonals
41	Sta	281 + 49	- 281 + 79	White Island Diagonals LT
33	Sta	282 + 18	- 282 + 47	White Island Diagonals RT
12	Sta	282 + 69	- 283 + 19	White Median Diagonals
<b>98</b>	<b>White Sub-Total</b>			
<b>2,325</b>	<b>TOTAL</b>			

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION			
	US 20 BR			
45	Sta	281 + 33		White Stop Bar
18	Sta	281 + 51		White Stop Bar
13	Sta	281 + 81		White Stop Bar
25	Sta	281 + 92		White Stop Bar
18	Sta	282 + 30		White Stop Bar
38	Sta	282 + 68		White Stop Bar
<b>157</b>	<b>TOTAL</b>			