

SCHEDULE OF QUANTITIES

TEMPORARY PAVEMENT MARKINGS

EACH	LOCATION			
	US 20 BR			
64	Sta	265 + 21	-	277 + 83
				One-way Amber LT & RT @ 40' o.c.
80	Sta	286 + 19	-	302 + 30
				One-way Amber LT & RT @ 40' o.c.
144 One-way Amber Total				
9	Sta	277 + 83	-	281 + 33
				Two-way Amber LT @ 40' o.c.
18	Sta	277 + 83	-	281 + 33
				Two-way Amber RT @ 20' o.c.
9	Sta	282 + 69	-	286 + 19
				Two-way Amber LT @ 40' o.c.
18	Sta	282 + 69	-	286 + 19
				Two-way Amber RT @ 20' o.c.
54 Two-way Amber Total				
18	Sta	277 + 83	-	281 + 33
				One-way Crystal RT @ 20' o.c.
16	Sta	278 + 30	-	281 + 33
				One-way Crystal RT @ 20' o.c.
15	Sta	282 + 69	-	285 + 54
				One-way Crystal LT @ 20' o.c.
18	Sta	282 + 69	-	286 + 19
				One-way Crystal LT @ 20' o.c.
67 One-way Crystal Total				

265 TOTAL

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION			
	US 20 BR			
EXISTING PAVEMENT MARKINGS				
73.3	Sta	256 + 00	-	264 + 64
				White Skip Dash - RT (Stage 2)
43.3	Sta	263 + 34	-	268 + 55
				White Skip Dash - LT (Stage 2)
458.3	Sta	267 + 00	-	280 + 75
				White EOP - RT (Stage 2)
343.3	Sta	268 + 55	-	273 + 70
				Double Yellow No Pass (Stage 2)
127.3	Sta	273 + 70	-	276 + 72
				Yellow No Pass LT w/ Skip Dash (Stage 2)
120.0	Sta	276 + 72	-	290 + 93
				Yellow Skip Dash
222.7	Sta	290 + 93	-	296 + 21
				Yellow No Pass RT w/ Skip Dash (Stage 2)
181.0	Sta	296 + 21	-	298 + 70
				Yellow Median w/ Diagonals (Stage 2)
370.7	Sta	298 + 70	-	300 + 88
				Double Yellow Median w/ Diagonals (Stage 2)
594.3	Sta	283 + 05	-	300 + 88
				White EOP - RT (Stage 2)
1,401.0	Sta	261 + 41	-	268 + 55
				Double Yellow Median w/ Diagonals (Stage 3)
370.0	Sta	269 + 70	-	280 + 80
				White EOP - LT (Stage 3)
515.7	Sta	282 + 90	-	298 + 37
				White EOP - LT (Stage 3)

632.0	Sta	263 + 34	-	281 + 80	White EOP - LT (Stage 2)
1,650.0	Sta	256 + 00	-	280 + 75	Double Yellow (Stage 2)
868.3	Sta	256 + 00	-	281 + 50	White EOP - RT (Stage 2)
644.3	Sta	282 + 20	-	300 + 88	White EOP - LT (Stage 2)
1,188.3	Sta	283 + 05	-	300 + 88	Double Yellow (Stage 2)
627.7	Sta	282 + 40	-	300 + 88	White EOP - RT (Stage 2)
590.0	Sta	264 + 70	-	281 + 80	White EOP - LT (Stage 3)
1,292.0	Sta	261 + 42	-	280 + 80	Double Yellow (Stage 3)
694.3	Sta	261 + 42	-	281 + 75	White EOP - RT (Stage 3)
557.3	Sta	282 + 15	-	298 + 37	White EOP - LT (Stage 3)
1,031.0	Sta	282 + 90	-	298 + 37	Double Yellow (Stage 3)
559.0	Sta	282 + 25	-	298 + 37	White EOP - RT (Stage 3)
400.0					As Needed & Directed by the Resident (Temp - Line 24")
15,555.3 TOTAL					

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION			
	US 20 BR			
100	Sta	265 + 21	-	302 + 30
100 TOTAL				

X0325702 NIGHTTIME WORK ZONE LIGHTING

L SUM	LOCATION			
	US 20 BR			
1	As Needed & Directed by the Resident			
1 TOTAL				

X0329907 PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/2"

SQ YD	LOCATION			
	US 20 BR			
132.4	Sta	280 + 26	-	280 + 76
				Mainline - 50' Taper
815.2	Sta	280 + 76	-	283 + 82
				Mainline w/ Returns
134.6	Sta	283 + 82	-	284 + 32
				Mainline - 50' Taper
1,082.2 TOTAL				