

EARTHWORK SCHEDULE

LOCATION	EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% CU YD	EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD
265 + 00 - 271 + 00	424	318	439	-121
271 + 00 - 281 + 00	1182	887	2,039	-1,153
282 + 50 - 286 + 00	443	332	291	41
286 + 00 - 299 + 50	1435	1,076	1,390	-314
TOTAL	3484	2,613	4,159	-1,546