



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.
Reinforcement bars designated (E) shall be epoxy coated.
Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
Existing reinforcement bars extending into the removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.
Joint openings shall be adjusted according to Article 520.04 of the Std. Specs. when the deck is poured at an ambient temperature other than 50° F.



ELEVATION



PLAN

TOTAL BILL OF MATERIAL

| ITEM | UNIT | QUANTITY |
|----------------------------------|---------|----------|
| Concrete Removal | Cu. Yd. | 20.6 |
| Concrete Superstructure | Cu. Yd. | 20.4 |
| Reinforcement Bars, Epoxy Coated | Pound | 3390 |
| Preformed Joint Strip Seal | Foot | 44 |
| Mechanical Splicers | Each | 116 |
| Bar Splicers | Each | 8 |

**PLAN & ELEVATION
U.S. ROUTE 6 OVER GENESEO CREEK
SN 037-0133**

DESIGNED *Alvan T. Holloway*
CHECKED *Jim J. Joply*
DRAWN *Kyle M. Steffen*
CHECKED *ATH ISL*

FEBRUARY 16, 2010
EXAMINED *Dr. Carl Brown*
PASSED *Robert E. Anderson*



Expires: November 30, 2010

| | | | | | |
|-------------------------|-------------|-----------|---------------------------|--------------|-----------|
| SHEET NO. 1 6 SHEETS | F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 5671 | (4B-1)R-M | HENRY | 13 | 6 |
| FED. ROAD DIST. NO. | | | ILLINOIS FED. AID PROJECT | | |

CONTRACT NO. 64F97