

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90/10 FED/ST CONSTRUCTION CODES			100% CITY J000
				J000	X271-2A	Y030-1E	
50300280	CONCRETE ENCASEMENT	CU YD	7		7.0		
50300300	PROTECTIVE COAT	SQ YD	1504		1,504		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	3552		3,552		
50800105	REINFORCEMENT BARS	POUND	3336	3,336			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	146590		146,590		
50800515	BAR SPLICERS	EACH	962		962		
51100100	SLOPE WALL 4 INCH	SQ YD	548		548		
51201600	FURNISHING STEEL PILES HP12X53	FOOT	909		909		
51201610	FURNISHING STEEL PILES HP12X63	FOOT	630		630		
51202305	DRIVING PILES	FOOT	1539		1,539		
51203600	TEST PILE STEEL HP12X53	EACH	2		2		
51203610	TEST PILE STEEL HP12X63	EACH	1		1		
51205200	TEMPORARY SHEET PILING	SQ FT	303		303		
51500100	NAME PLATES	EACH	1		1		
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2	2			
54002020	EXPANSION BOLTS 3/4 INCH	EACH	96	96			
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	12	12.0			
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	55	55			

* SPECIALTY ITEMS

© Copyright Hanson Professional Services Inc. 2002. YEARS



Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

MODEL NAME = #MODEL#
PLOT DATE = Feb 17, 2008 - 02:57:44 PM
PLOT SCALE = 50.0000 / IN.
USER NAME = carpenterd

LAYOUT	RDJ	12/14/05
DRAWN	RDJ	12/14/05
REVIEWED	MTM	10/1/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -4

SCALE: VERT. N/A
HORIZ. N/A
DATE

DRAWN BY RDJ
CHECKED BY