

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90/10 FED/ST CONSTRUCTION CODES			
				J000	X271-2A	Y030-1E	100% CITY J000
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1	
* 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	380			380	
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	428			428	
* 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	1			1	
* 81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	7,893			7,893	
* 81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,502			2,502	
* 81603070	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	8,038			8,038	
* 81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2,360			2,360	
* 81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,790			1,790	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	17,075			17,075	
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	21			21	
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	9			9	
* 82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	114			114	
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	4			4	
* 82109105	SIGN LIGHTING (HIGH PRESSURE SODIUM)	EACH	3			3	
* 82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1			1	
* 83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	9			9	
* 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	22			22	
* 83502300	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 4	EACH	3			3	

\* SPECIALTY ITEMS

© Copyright Hanson Professional Services Inc. 2002. YEARS



Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Offices Nationwide

MODEL NAME = #MODEL  
PLOT DATE = Feb 17, 2010 - 02:56:42 PM  
FILE NAME = c:\p\work\PROJECT\CURRENT\RDJ\dms1493\Revised Summary.dgn  
PLOT SCALE = 50:0000 - 1/4" = 1'-0"  
USER NAME = c:\p\work\PROJECT\CURRENT\RDJ\dms1493\Revised Summary.dgn

LAYOUT	RDJ	12/14/05
DRAWN	RDJ	12/14/05
REVIEWED	WTN	10/17/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -11

SCALE: VERT. N/A  
HORIZ. N/A

DATE

DRAWN BY RDJ  
CHECKED BY