CONTRACT NO 66542

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	30
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVING SCHEDULE -1

LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	AGGREGATE BASE COURSE, TYPE A	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/4"	HOT-MIX ASPHALT SHOULDERS, 13 3/4"	HOT-MIX ASPHALT SHOULDERS, 6"	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	HOT-MIX ASPHALT SURFACE COURSE MIX D N70
	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GAL)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
EASTBOUND I-80												
STA TO						1431.25						
STA 869+57.86 19.90 RT TO 30+89.60 19.56 RT	4127.4							3816.5				
STA 876+21.44 49.00 RT TO 883+10.66 85.77 RT								472.0				
STA 876+21.44 48.00 RT TO 887+30.05 48.00 RT		2488.1				933.02						
STA 876+21.62 48.00 RT TO 883+12.04 48.00 RT							1489.6					
STA 883+12.82 48.00 RT TO 887+30.01 48.00 RT								464.6				
STA 905+55.87 48.00 RT TO 26+16.02 48.00 RT		3482.5				1305.95						
STA 905+55.87 48.00 RT TO 908+81.05 48.00 RT								361.3				
STA 908+81.06 48.00 RT TO 26+14.68 48.00 RT							2122.1					
STA 908+84.80 81.40 RT TO 26+16.02 49.00 RT								907.5				
SUBTOTAL	4127.4	5970.6				3670.23	3611.7	6022.1				
WESTBOUND I-80												
STA 866+05.68 20.08 LT TO 24+98.57 20.43 LT	3962.1							3657.3				
STA						1371.50						
STA 869+66.83 49.00 LT TO 883+01.03 81.39 LT								911.6				
STA 869+66.83 48.00 LT TO 886+13.82 48.00 LT		3441.3				1290.49						
STA 869+66.99 48.00 LT TO 883+04.86 48.00 LT							2095.2					
STA 883+04.68 48.00 LT TO 886+13.82 48.00 LT								343.5				
STA 905+20.03 48.00 LT TO 19+56.74 48.00 LT		2391.1				896.66						
STA 905+20.05 48.00 LT TO 908+59.83 48.00 LT								377.5				
STA 908+59.81 48.00 LT TO 19+56.74 48.00 LT							1487.4					
STA 908+61.32 85.79 LT TO 19+58.08 49.00 LT								469.0				
SUBTOTAL	3962.1	5832.4				3558.65	3582.6	5758.9				
RAMP I												
STA 201+44.94 20.99 LT TO 213+82.19 20.00 LT		849.7			3572.7	1339.77				2198.9		
STA 201+44.94 BL TO 213+82.19 BL											825.1	
STA 201+44.94 16.99 LT TO 213+82.19 16.00 LT											548.7	
STA 213+82.00 TO 227+14.00			2723.0									
SUBTOTAL		849.7	2723.0		3572.7	1339.77				2198.9	1373.8	
RAMP J												
STA 306+60.09 20.00 LT TO 319+10.93 20.00 LT		2332.3			3838.8	1439.54				2446.6		
STA 306+60.09 BL TO 319+10.93 BL											834.5	
STA 306+60.09 16.00 LT TO 319+10.93 16.00 LT											557.7	
STA 299+70.00 TO 306+60.00			1506.5									
SUBTOTAL		2332.3	1506.5		3838.8	1439.54				2446.6	1392.2	
RAMP K												
STA 406+62.82 20.00 LT TO 418+79.04 20.00 LT		2264.5			3777.6	1416.58				2424.4		
STA 406+63.04 BL TO 418+79.04 8.00 RT											810.0	
STA 406+63.04 16.00 LT TO 418+79.04 16.00 LT											543.1	
STA 399+69.00 TO 406+63.00			1513.0									
SUBTOTAL		2264.5	1513.0		3777.6	1416.58				2424.4	1353.1	
RAMP L												
STA 501+41.36 24.78 LT TO 513+72.71 20.00 LT		834.6			3582.4	1343.40				2213.1		
STA 501+41.36 BL TO 513+72.71 BL											820.5	
STA 501+41.36 20.77 LT TO 513+72.71 16.00 LT											548.8	
STA 513+73.00 TO 526+97.00			2747.8									
SUBTOTAL		834.6	2747.8		3582.4	1343.40				2213.1	1369.3	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES-4

SCALE: VERT. N/A HORIZ. N/A

DATE

DRAWN BY RDJ

CHECKED BY

© Copyright Hanson Professional Services Inc. 2009

HANSON
Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

MODEL NAME = Sheet 9a
PLOT DATE = 10/21/2009
FILE NAME = C:\Pw_Export\C_6015C1.dgn
PLOT SCALE = 50.0000 ' / in.
USER NAME = Johnsa00944

LAYOUT	RDJ	01/20/06
DRAWN	RDJ	01/20/06
REVIEWED	MTW	10/21/07