

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	35
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKING I-80 AND RAMPS SCHEDULE 1							THERMOPLASTIC PAVEMENT MARKING - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"
							(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
EASTBOUND I-80															
STA	19+08.45	24.00'	RT	TO	30+89.60	24.00'	RT	1181.2							
STA	19+08.45	63.56'	RT	TO	30+89.60	48.00'	RT	1181.2							
STA	869+57.86	36.00'	RT	TO	30+89.60	36.00'	RT		1430.8						
STA	869+57.86	48.00'	RT	TO	883+10.98	86.05'	RT	1353.1							
STA	869+57.86	24.00'	RT	TO	915+00.00	24.00'	RT	4542.1							
STA	876+01.58	48.20'	RT	TO	879+04.64	48.25'	RT		75.8						
STA	879+04.64	48.25'	RT	TO	883+11.85	48.28'	RT		407.2						
STA	879+04.64	48.25'	RT	TO	883+11.85	70.08'	RT		407.2						
STA	883+11.85	48.28'	RT	TO	908+81.64	48.39'	RT	2569.8							
STA	908+31.07	48.38'	RT	TO	914+57.46	48.41'	RT		626.4						
STA	908+32.42	74.73'	RT	TO	914+57.46	48.41'	RT		625.0						
STA	908+83.95	81.78'	RT	TO	915+00.00	63.56'	RT	616.1							
WESTBOUND I-80															
STA	19+08.45	47.59'	LT	TO	19+76.79	47.59'	LT		17.1						
STA	19+08.45	24.00'	LT	TO	24+98.57	24.00'	LT	590.1							
STA	19+08.45	51.24'	LT	TO	24+98.57	47.57'	LT	590.1							
STA	866+05.68	36.00'	LT	TO	24+98.57	36.00'	LT		1371.1						
STA	866+05.68	47.92'	LT	TO	883+01.87	81.11'	LT	1696.2							
STA	866+05.68	24.00'	LT	TO	915+00.00	24.00'	LT	4894.3							
STA	877+68.92	47.77'	LT	TO	883+04.11	65.27'	LT		535.2						
STA	877+68.92	47.77'	LT	TO	883+04.11	47.72'	LT		535.2						
STA	883+04.11	47.72'	LT	TO	908+59.83	47.62'	LT	2555.7							
STA	908+59.83	47.61'	LT	TO	912+68.37	47.60'	LT		408.5						
STA	908+60.04	69.42'	LT	TO	912+68.37	47.60'	LT		408.3						
STA	908+60.90	85.40'	LT	TO	915+00.00	51.24'	LT	639.1							
STA	912+68.37	47.60'	LT	TO	915+00.00	47.59'	LT		57.9						
RAMP I															
STA	200+23.00	49.23'	LT	TO	201+73.00	16.00'	LT			159.1					
STA	200+35.00	62.50'	RT	TO	201+44.95	0.00'	CL			137.2					
STA	201+73.00	16.00'	LT	TO	213+82.19	16.00'	LT			1209.2					
STA	201+44.95	0.00'	CL	TO	213+82.19	0.00'	CL			1237.2					
RAMP J															
STA	306+60.09	0.00'	CL	TO	319+10.93	8.00'	RT			1250.8					
STA	308+10.09	16.00'	LT	TO	319+10.93	16.00'	LT			1100.8					
STA	315+63.85	0.00'	CL	TO	317+74.87	4.00'	LT				52.8				
STA	317+74.87	4.00'	LT	TO	319+10.93	4.00'	LT				136.1				
STA	317+92.40	2.01'	RT	RIGHT TURN ARROW					15.6						
STA	317+92.43	10.20'	LT	LEFT TURN ARROW					15.6						
STA	318+95.28	2.37'	RT	RIGHT TURN ARROW					15.6						
STA	318+95.43	10.09'	LT	LEFT TURN ARROW					15.6						
STA	319+10.93	16.00'	LT	TO	319+84.67	54.54'	LT			86.5					
STA	319+10.93	8.00'	RT	TO	320+23.09	113.28'	RT			176.3					
STA	319+64.86	23.89'	LT	LEFT TURN ARROW					15.6						
STA	319+69.64	5.84'	RT	RIGHT TURN ARROW					15.6						
RAMP K															
STA	406+63.04	0.00'	CL	TO	418+79.04	8.00'	RT			1216.0					
STA	407+13.04	16.00'	LT	TO	418+79.04	16.00'	LT			1166.0					
STA	415+28.76	0.00'	CL	TO	416+48.76	4.00'	LT				30.0				
STA	416+48.76	4.00'	LT	TO	418+79.04	4.00'	LT				230.3				
STA	416+80.49	9.95'	LT	LEFT TURN ARROW					15.6						
STA	416+80.51	2.09'	RT	RIGHT TURN ARROW					15.6						
STA	417+75.82	1.54'	RT	RIGHT TURN ARROW					15.6						
STA	417+76.29	10.17'	LT	LEFT TURN ARROW					15.6						
STA	418+70.70	1.80'	RT	RIGHT TURN ARROW					15.6						
STA	418+70.91	10.13'	LT	LEFT TURN ARROW					15.6						
STA	418+79.04	16.00'	LT	TO	419+57.82	62.48'	LT			95.9					
STA	418+79.04	8.00'	RT	TO	420+06.37	117.14'	RT			203.8					
STA	419+39.26	27.41'	LT	LEFT TURN ARROW					15.6						
STA	419+43.75	1.55'	RT	RIGHT TURN ARROW					15.6						
RAMP L															
STA	500+20.42	47.56'	RT	TO	501+41.36	0.00'	CL			137.2					
STA	500+52.69	80.77'	LT	TO	501+41.36	20.77'	LT			114.5					
STA	501+41.36	20.77'	LT	TO	513+23.73	16.00'	LT			1182.4					
STA	501+41.36	0.00'	CL	TO	513+72.71	0.00'	CL			1231.4					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES-9

SCALE: VERT. N/A
HORIZ. N/A

DATE _____ DRAWN BY RDJ
CHECKED BY _____

© Copyright Hanson Professional Services Inc. 2009
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide
 MODEL NAME = Sheet 6'
 PLOT DATE = 12/23/2009
 PLOT SCALE = 50.0000"
 USER NAME = jsh400944
 LAYOUT: RDJ 01/20/06
 DRAWN: RDJ 01/20/06
 REVIEWED: MTM 10/1/07