

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	48
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PIPE UNDERDRAIN SCHEDULE

LOCATION							PIPE UNDERDRAINS 4" (FT)	PIPE UNDERDRAINS (SPECIAL) 4" (FT)	PIPE UNDERDRAINS 6" (FT)	PIPE UNDERDRAINS (SPECIAL) 6" (FT)	CONCRETE HEADWALL FOR PIPE DRAINS (EA)	COMMENT
STATION	OFFSET	SIDE	TO	STATION	OFFSET	SIDE						
F.A.I.-80												
869+16.00	8.00	LT										PRESTAGE PH I
870+00.00	8.00	LT										PRESTAGE PH I
870+48.00	8.00	RT										PRESTAGE PH I
874+99.00	8.00	RT										PRESTAGE PH I
875+00.00	8.00	LT										PRESTAGE PH I
879+98.00	8.00	RT										PRESTAGE PH I
880+00.50	8.00	LT										PRESTAGE PH I
884+97.00	8.00	RT										PRESTAGE PH I
885+00.00	8.00	LT										PRESTAGE PH I
886+14.00	64.00	LT							16	1		PRESTAGE PH I
886+14.00	48.50	LT		883+05.00	65.00	LT		309				PRESTAGE PH I
887+30.00	48.50	RT		883+00.00	48.50	RT		430				PRESTAGE PH I
889+97.00	8.00	RT										PRESTAGE PH I
890+00.00	8.00	LT										PRESTAGE PH I
894+97.00	8.00	RT										PRESTAGE PH I
895+00.00	8.00	LT										PRESTAGE PH I
899+97.00	8.00	RT										PRESTAGE PH I
899+99.00	8.00	LT										PRESTAGE PH I
905+00.00	8.00	RT										PRESTAGE PH I
905+00.00	8.00	LT										PRESTAGE PH I
905+05.00	66.00	LT							30	1		PRESTAGE PH I
905+55.00	66.00	RT							16	1		PRESTAGE PH I
908+60.00	48.50	LT		905+20.00	48.50	LT		340				PRESTAGE PH I
908+81.00	48.50	RT		905+56.00	48.50	RT		325				PRESTAGE PH I
909+96.00	8.00	RT										PRESTAGE PH I
909+99.00	8.00	LT										PRESTAGE PH I
914+96.00	8.00	RT										PRESTAGE PH I
914+98.00	8.00	LT										PRESTAGE PH I
26+15.00	48.50	RT		905+56.00	48.50	RT		1652				PRESTAGE PH I
SUBTOTAL							0	0	3056	62	3	
RAMP I												
201+33.00	0.50	RT		227+14.00	0.50	RT	2577					STAGE 2 PH I
201+33.00	16.00	LT		212+00.00	16.00	LT	1067					STAGE 2 PH I
206+30.00	32.00	LT						16		1		STAGE 2 PH I
206+30.00	16.00	RT						16		1		STAGE 2 PH I
211+30.00	32.00	LT						16		1		STAGE 2 PH I
211+97.00	16.00	RT						16		1		STAGE 2 PH I
212+00.00	16.00	LT		213+82.00	16.00	LT		182				STAGE 2 PH I
216+30.00	16.00	RT						16		1		STAGE 2 PH I
221+30.00	16.00	RT						16		1		STAGE 2 PH I
227+13.00	16.00	RT						16		1		STAGE 2 PH I
SUBTOTAL							3644	112	182	0	7	
RAMP J												
299+70.00	0.50	RT		310+30.00	0.50	RT	1060					STAGE 1 PH I
299+71.00	16.00	RT						16		1		STAGE 1 PH I
306+60.00	16.50	LT		310+30.00	16.50	LT	370					STAGE 1 PH I
310+29.00	16.00	RT						30		1		STAGE 1 PH I
310+29.00	32.00	LT						30		1		STAGE 1 PH I
315+25.00	32.00	LT						16		1		STAGE 1 PH I
315+25.00	16.00	RT						16		1		STAGE 1 PH I
319+10.00	0.50	RT		310+30.00	0.50	RT	880					STAGE 1 PH I
319+10.00	16.50	LT		310+30.00	16.50	LT	880					STAGE 1 PH I
SUBTOTAL							3190	108	0	0	5	
RAMP K												
399+70.00	16.00	RT						16		1		STAGE 2 PH I
402+35.00	16.00	RT						16		1		STAGE 2 PH I
406+50.00	16.00	LT		407+35.00	16.00	LT	85					STAGE 2 PH I
407+35.00	0.50	RT		399+69.00	0.50	RT	766					STAGE 2 PH I
407+35.00	0.50	RT		409+60.00	0.50	RT	225					STAGE 2 PH I
407+35.00	16.00	LT		409+60.00	16.00	LT	225					STAGE 2 PH I
409+60.00	32.00	LT						30		1		STAGE 2 PH I
409+60.00	16.00	RT						30		1		STAGE 2 PH I
418+79.00	0.50	RT		409+60.00	0.50	RT	919					STAGE 2 PH I
418+79.00	16.50	LT		409+60.00	16.50	LT	919					STAGE 2 PH I
SUBTOTAL							3139	92	0	0	4	
RAMP L												
501+37.00	0.50	RT		511+21.00	0.50	RT	984					STAGE 1 PH I
501+37.00	21.50	LT		511+21.00	16.50	LT	984					STAGE 1 PH I
506+25.00	32.00	LT						16		1		STAGE 1 PH I
506+25.00	16.00	RT						16		1		STAGE 1 PH I

© Copyright Hanson Professional Services Inc. 2009
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

MODEL NAME = Pipe Underdrain 1
 PLOT DATE = 12/23/2009
 PLOT SCALE = 50:800
 USER NAME = JohnM02544
 LAYOUT: KET 01/20/06
 DRAWN: KET 01/20/06
 REVIEWED: MTW 10/1/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE UNDERDRAINS SCHEDULE -1

SCALE: VERT. N/A
 HORIZ. N/A

DRAWN BY KET
 CHECKED BY