

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	150-3H8K	LASALLE	492	233
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BILL OF MATERIALS - REMOVALS

SIGN REMOVAL NUMBER	ALIGNMENT NAME	STATION	LOCATION (LEFT, RIGHT, MEDIAN)	PANEL WIDTH FEET	PANEL HEIGHT FEET	SIGN AREA SQ. FT.	POST MATERIAL	REMOVE SIGN PANEL ASSEMBLY TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY TYPE B EACH	REMOVE SIGN PANEL TYPE 1 SQ. FT.	REMOVE SIGN PANEL TYPE 2 SQ. FT.	REMOVE SIGN PANEL TYPE 3 SQ. FT.	REMOVE OVERHEAD SIGN STRUCTURE SPAN EACH	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	REMOVE CONCRETE FOUNDATION GROUND MOUNT EACH	REMOVE CONCRETE FOUNDATION OVERHEAD EACH	REMARKS
001	I-80 WB	871+86	LEFT	2.00	1.00	2.00	WOOD		1					1			
				3.00	3.00	9.00											
002	I-80 EB	886+61	RIGHT	5.00	6.00	30.00	WOOD					30.00		2			
003	I-80 WB	888+03	LEFT	4.00	4.00	16.00	WOOD				16.00			1			
004	I-80 EB	888+55	RIGHT	1.00	3.00	3.00	STEEL			3.00				1			
005	I-80 WB	889+00	LEFT	1.00	3.00	3.00	STEEL			3.00				1			
006	I-80 EB	903+70	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
007	I-80 WB	905+16	LEFT	6.00	5.00	30.00	WOOD					30.00		2			
				6.00	2.00	12.00											
				6.00	2.00	12.00											
				6.00	1.00	6.00							1			2	
				9.00	9.00	81.00											
				30.00	10.00	300.00											
008	I-80 WB	907+73	LEFT	2.00	1.00	2.00											
009	I-80 EB	23+70	RIGHT	3.00	3.00	9.00	WOOD		1					1			
010	RAMP I	200+87	RIGHT	5.00	4.00	20.00	WOOD				20.00			2			
011	RAMP I	202+11	RIGHT	2.00	2.50	5.00	WOOD			5.00				1			
012	RAMP I	205+23	RIGHT	1.50	1.25	1.88	STEEL			1.88				1			
014	RAMP I	207+79	RIGHT	1.50	1.25	1.88	STEEL			1.88				1			
015	RAMP J	305+85	RIGHT	4.00	8.00	32.00	WOOD					32.00		2			
016	RAMP J	307+39	RIGHT	9.00	10.00	90.00	STEEL					90.00		2	2		
017	RAMP J	309+04	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
018	RAMP J	310+62	RIGHT	11.00	11.00	121.00	STEEL					121.00		2	2		
				15.00	8.00	120.00						120.00					
019	RAMP J	312+99	RIGHT	2.00	2.00	4.00	STEEL			4.00				2	2		
				2.00	1.00	2.00			2.00								
				6.50	2.00	13.00				13.00							
020	RAMP J	314+84	RIGHT	10.00	5.00	50.00	STEEL					50.00		2	2		
021	RAMP J	315+45	LEFT	3.00	2.00	6.00	WOOD			6.00				1			
022	RAMP J	315+47	RIGHT	3.00	2.00	6.00	WOOD			6.00				1			
023	RAMP J	316+20	RIGHT	3.00	1.50	4.50	WOOD		1					1			
				3.00	3.00	9.00											
024	RAMP J	316+24	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
025	RAMP J	316+85	RIGHT	2.50	2.50	6.25	WOOD			6.25				1			
				2.50	2.50	6.25											
026	RAMP J	316+87	LEFT	3.00	1.00	3.00	WOOD		1					1			
				1.50	2.00	3.00											
				3.00	1.00	3.00											
027	RAMP K	405+81	RIGHT	8.00	2.00	16.00	STEEL				16.00	90.00		2	2		
				9.00	10.00	90.00											
028	RAMP K	407+22	RIGHT	6.00	10.00	60.00	STEEL					60.00		2	2		
029	RAMP K	409+03	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
030	RAMP K	411+07	RIGHT	10.00	8.00	80.00	STEEL					80.00		2	2		
				14.00	8.00	112.00						112.00					
031	RAMP K	413+05	RIGHT	2.00	1.00	2.00	STEEL			2.00				2	2		
				2.00	2.00	4.00			4.00								
				7.00	2.00	14.00				14.00							
032	RAMP K	414+96	RIGHT	11.00	6.00	66.00	STEEL					66.00		2	2		
033	RAMP K	415+58	LEFT	3.00	2.00	6.00	WOOD			6.00				1			
034	RAMP K	415+63	RIGHT	3.00	2.00	6.00	WOOD			6.00				1			
035	RAMP K	416+32	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
036	RAMP K	416+35	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
SUBTOTAL								0	4	111.01	79.00	881.00	1	47	18	2	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGNING PLAN  
BILL OF MATERIALS  
REMOVALS

SCALE: VERT.  
HORIZ. N.T.S.  
DATE

DRAWN BY MOC  
CHECKED BY MLT



MODEL NAME = 2 Removal 1  
 PLOT DATE = 10/23/2009  
 PLOT SCALE = 1/2" = 1'-0"  
 USER NAME = jehna209144  
 LAYOUT MOC 02/08/06  
 DRAWN MOC 02/08/06  
 REVIEWED MLT 10/1/07