

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(3)BR-1	LASALLE	44	6
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 66619

SCHEDULE OF QUANTITIES

<u>ENGINEER'S FIELD OFFICE, TYPE A</u>	
8 CAL MO	
<u>MOBILIZATION</u>	
1 LUMP SUM	
<u>TRAFFIC CONTROL AND PROTECTION, STANDARD 701321</u>	
1 EACH	
<u>TRAFFIC CONTROL AND PROTECTION, STANDARD 701306</u>	
1 LUMP SUM	
<u>TEMPORARY BRIDGE TRAFFIC SIGNALS</u>	
LOCATION	EACH
(SEE STAGE CONSTRUCTION DETAILS)	1
TOTAL	1
<u>SHORT-TERM PAVEMENT MARKING</u>	
LOCATION	FOOT
YELLOW (2 COURSES)	
(ONE 4' STRIPE PER 40' OF ROAD)	180
TOTAL	180
<u>TEMPORARY PAVEMENT MARKING - LINE 4"</u>	
LOCATION	FOOT
WHITE (LANE LINES)	
LT. STA. 415+50 TO STA. 424+50	900
RT. STA. 415+50 TO STA. 424+50	900
YELLOW (DOUBLE CENTERLINE)	
☉ STA. 415+50 TO STA. 420+56.7	1,014
YELLOW (SOLID)	
☉ STA. 420+56.7 TO STA. 422+71.7	215
YELLOW (SKIP-DASH)	
☉ STA. 420+56.7 TO STA. 424+50	100
TOTAL	3,129
<u>WORK ZONE PAVEMENT MARKING REMOVAL</u>	
LOCATION	SQ FT
REMOVE SHORT-TERM PAVEMENT MARKING	30
TOTAL	30
<u>TEMPORARY CONCRETE BARRIER</u>	
LOCATION	FOOT
(SEE STAGE CONSTRUCTION DETAILS)	
<u>STAGE I</u>	
STA. 418+42 TO STA. 421+62	320
<u>STAGE II</u>	
STA. 417+69 TO STA. 418+42	73
STA. 421+62 TO STA. 422+35	73
TOTAL	466
<u>RELOCATE TEMPORARY CONCRETE BARRIER</u>	
LOCATION	FOOT
(SEE STAGE CONSTRUCTION DETAILS)	
<u>STAGE II</u>	
STA. 418+42 TO STA. 421+62	320
TOTAL	320
<u>PAINT PAVEMENT MARKING - LINE 4"</u>	
LOCATION	FOOT
WHITE (LANE LINES)	
LT. STA. 415+50 TO STA. 424+50	900
RT. STA. 415+50 TO STA. 424+50	900
YELLOW (DOUBLE CENTERLINE)	
☉ STA. 415+50 TO STA. 420+56.7	1,014
YELLOW (SOLID)	
☉ STA. 420+56.7 TO STA. 422+71.7	215
YELLOW (SKIP-DASH)	
☉ STA. 420+56.7 TO STA. 424+50	100
TOTAL	3,129

<u>RAISED REFLECTIVE PAVEMENT MARKER</u>	
LOCATION	EACH
(BASED ON 1 MARKER EVERY 80')	
☉ STA. 415+50 TO ☉ STA. 418+93	5
☉ STA. 420+67 TO ☉ STA. 424+50	5
TOTAL	10

<u>RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)</u>	
LOCATION	EACH
(BASED ON 1 MARKER EVERY 80')	
☉ STA. 418+93 TO ☉ STA. 420+67	3
TOTAL	3

<u>GUARDRAIL MARKERS, TYPE A</u>	
(BASED ON 80' SPACING - MIN. 4)	
	MONO DIRECTIONAL SILVER
LOCATION	EACH
LT. STA. 418+29.89 TO LT. STA. 419+25.50	4
RT. STA. 416+67.39 TO RT. STA. 419+25.50	4
LT. STA. 420+39.50 TO LT. STA. 422+97.61	4
RT. STA. 420+39.50 TO RT. STA. 422+10.11	4
TOTAL	16

<u>BARRIER WALL MARKERS, TYPE B</u>	
(BASED ON 80' SPACING - MIN. 4)	
	MONO DIRECTIONAL SILVER
LOCATION	EACH
LT. STA. 419+25.50 TO LT. STA. 420+39.50	4
RT. STA. 419+25.50 TO RT. STA. 420+39.50	4
TOTAL	8

<u>TERMINAL MARKER - DIRECT APPLIED</u>	
LOCATION	EACH
STA. 418+29.89 LT	1
STA. 416+67.39 RT	1
STA. 422+97.61 LT	1
STA. 422+10.11 RT	1
TOTAL	4

<u>RAISED REFLECTIVE PAVEMENT MARKER REMOVAL</u>	
LOCATION	EACH
(BASED ON 1 MARKER EVERY 80')	
	11
TOTAL	11

<u>IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3</u>	
LOCATION	EACH
<u>STAGE I</u>	
LT. STA. 417+35	1
LT. STA. 421+62	1
TOTAL	2

<u>IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3</u>	
LOCATION	EACH
<u>STAGE I</u>	
LT. STA. 418+21	1
EACH	1

<u>IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3</u>	
LOCATION	EACH
<u>STAGE II</u>	
RT. STA. 417+19	1
RT. STA. 422+35	1
EACH	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 SCALE: NONE
 DATE: JUNE 20, 2008
 DRAWN BY: DAC
 CHECKED BY: AAG