

F.A.U. / RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAL 80	50-8HBR	LASALLE	142	48
STA.	TO STA.			
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				

IDOT PAY ITEM NO.	DESIGNATION	UNIT	CONTRACT TOTAL
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	54
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	454
81104600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., INTERMEDIATE METAL	FOOT	240
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	12
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2534
81603070	UNIT DUCT, 600V, 2-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1/4" DIA. POLYETHYLENE	FOOT	2195
81603095	UNIT DUCT, 600V, 4-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1/2" DIA. POLYETHYLENE	FOOT	875
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	783
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	256
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	2055
* 81800185	AERIAL CABLE, 2-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	1566
81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	827
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5425
82102100	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 100 WATT	EACH	18
82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	9
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	9
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1
83001400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. DAVIT ARM	EACH	2
83002400	LIGHT POLE, ALUMINUM, 40 FT. M.H., 10 FT. DAVIT ARM	EACH	4
* 83000010	LIGHT POLE, ALUMINUM, 16 FT. M.H., 6 FT. DAVIT ARM	EACH	2
* 83000015	LIGHT POLE, ALUMINUM, 16 FT. M.H., 10 FT. DAVIT ARM	EACH	2
* 83000020	LIGHT POLE, ALUMINUM, 17 FT. M.H., 10 FT. DAVIT ARM	EACH	3
* 83000025	LIGHT POLE, ALUMINUM, 18 FT. M.H., 10 FT. DAVIT ARM	EACH	4
* 83000030	LIGHT POLE, ALUMINUM, 20 FT. M.H., 6 FT. DAVIT ARM	EACH	3
* 83000035	LIGHT POLE, ALUMINUM, 20 FT. M.H., 10 FT. DAVIT ARM	EACH	3
83057145	LIGHT POLE, WOOD, 30 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	10
83057150	LIGHT POLE, WOOD, 30 FOOT, CLASS 4	EACH	4
83057285	LIGHT POLE, WOOD, 50 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	3
83057290	LIGHT POLE, WOOD, 50 FOOT, CLASS 4	EACH	4
83600350	LIGHT POLE FOUNDATION METAL, 11" BOLT CIRCLE, 8" X 6'	EACH	26
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	4
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	120
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	13
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	6
84200804	REMOVAL OF POLE FOUNDATION	EACH	18
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	12
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1
* X0322141	REMOVE TEMPORARY WOOD POLE	EACH	9
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	9
* X8450100	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	1

\* INDICATES SPECIAL PROVISION.

NOTE:

THE SUMMARY OF QUANTITIES INCLUDES THE UNIT DUCTS, CONDUITS, AND OTHER ITEMS USED IN TEMPORARY LIGHTING.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION PLANK ROAD OVER I-80
NAME	DATE	
		SUMMARY OF QUANTITIES
SCALE: None		DRAWN BY: RDP
DATE: 12/2/2009		CHECKED BY: PKG