

SUMMARY OF QUANTITIES

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	90% FED. 10% STATE	1000	
			TOTAL QUANTITY	LASALLE QUANTITY	GRUNDY QUANTITY
50300225	CONCRETE STRUCTURES	CU YD	68	49	19
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8547	6105	2442
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	5675	4275	1400
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	200	150	50
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	15	11	4
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	3	1	2
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	14	11	3
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	24	19	5
63200310	GUARDRAIL REMOVAL	FOOT	7995	6045	1950
63500105	DELINEATORS	EACH	242	176	66
63500120	DELINEATOR REMOVAL	EACH	242	176	66
64200105	SHOULDER RUMBLE STRIP	FOOT	183,329	133,994	49,335
66500105	WOVEN WIRE FENCE, 4'	FOOT	7800	5400	2400
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	7800	5400	2400
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	8	4
67100100	MOBILIZATION	L SUM	1	0.7	0.3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14	10	4
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	8	4	4
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	32	22	10
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	187,328	135,994	51,334
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	23,416	16,999	6417
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	5490	2820	2670
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1014		1014
* 70300505	PAVEMENT MARKING TAPE, TYPE III (SPECIAL)	FOOT	24,364	17,685	6679
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8121	5895	2226
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2480	1771	709
* 78200405	GUARDRAIL MARKERS	EACH	105	80	25

* SPECIALTY ITEM