

GUARDRAIL SCHEDULE									
CULVERT OR PIER LOCATION	GUARDRAIL	SPBGR,	SPBGR ATT.	TBT TY 1	TBT TY	TBT TY	TBT TY	G-RAIL	TERMINAL
	REMOVAL	TYPE A	TO STRUCT.	SPEC (TANG)	2	5	6B	MARKERS	MARKER - DA
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
LASALLE COUNTY									
STA 885+07 WB	550	425		1	1	1	1	7	1
STA 885+07 MED	45.4								
STA 885+07 EB	426	325		1			1	5	1
STA 937+90 WB	285	225		1			1	4	1
STA 937+90 MED	45.4								
STA 937+90 EB	317	225		1			1	4	1
STA 948+28 WB	240	175	12.5	1	1			4	1
STA 948+28 EB	221	175	12.5	1	1			4	1
STA 983+00 WB	244	175	25	1	1			4	1
STA 983+00 EB	260	175	25	1	1			4	1
STA 990+89 WB	278	225		1			1	4	1
STA 990+89 MED	45.4								
STA 990+89 EB	308	225		1			1	4	1
STA 1001+70 WB	339	250	25	1	1			4	1
STA 1001+70 EB	304	237.5	25	1	1			4	1
STA 1044+01 WB	291	225		1			1	4	1
STA 1044+01 MED	45.4								
STA 1044+01 EB	290	225		1			1	4	1
STA 1096+98 WB	291	225		1			1	4	1
STA 1096+98 MED	45.4								
STA 1096+98 EB	255	125		1	2		1	4	1
STA 1110+00 WB	253	187.5	12.5	1	1			4	1
STA 1110+00 EB	267	200	12.5	1	1			4	1
STA 1149+99 EB	354	250		1			1	4	1
STA 1149+99 MED	45.4								
LASALLE CO. SUBTOTAL	6045.4	4275	150	19	11	1	11	80	19
GRUNDY COUNTY									
STA 1149+99 EB	114	87.5			1	1		2	
STA 1149+99 WB	416	300	12.5	1			1	5	1
STA 751+90 WB	252	200	18.75	1	1			4	1
STA 751+90 EB	278	200	18.75	1	1			4	1
STA 766+60 WB	498	362.5		1	1	1	1	6	1
STA 766+60 MED	45.4								
STA 766+60 EB	346	250		1			1	4	1
GRUNDY CO SUBTOTAL	1949.4	1400	50	5	4	2	3	25	5
PROJECT TOTALS	7995	5675	200	24	15	3	14	105	24

UNDER THE GUARDRAIL REMOVAL PAY ITEM, ANY EXISTING GUARDRAIL THAT IS ATTACHED TO STRUCTURES WILL NOT BE PAID FOR SEPERATELY BUT WILL BE PAID FOR AS GUARDRAIL REMOVAL.

ALL BOLT HOLES IN THE PIERS FROM THE REMOVAL OF THE EXISTING TRAFFIC BARRIER TERMINALS SHALL BE EPOXY GROUTED PRIOR TO THE INSTALLATION OF THE NEW TRAFFIC BARRIER TERMINALS.

CONC. AND REBAR SCHEDULE (CRASH WALLS)								
LOCATIONS	EB	MED	WB	TOTAL	EB	MED	WB	TOTAL
	CONC	CONC	CONC	CONC	REBAR	REBAR	REBAR	REBAR
	CY	CY	CY	CY	POUND	POUND	POUND	POUND
LASALLE COUNTY								
050-0132	2.93	3.91	3.12	9.96	407	407	407	1221
050-0133	2.93	2.74	3.12	8.79	407	407	407	1221
050-0134	3.12	3.91	3.12	10.15	407	407	407	1221
050-0135	2.93	3.32	3.52	9.77	407	407	407	1221
050-0105	3.32	3.52	3.12	9.96	407	407	407	1221
LASALLE CO. SUBTOTAL				48.63				6105
GRUNDY COUNTY								
032-0053	3.12	3.12	3.32	9.56	407	407	407	1221
032-0052	3.12	3.52	3.12	9.76	407	407	407	1221
GRUNDY CO SUBTOTAL				19.32				2442
PROJECT TOTALS				68				8547