

MEDIAN EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (CUT)	EARTH EX. ADJUSTED FOR SHRINKAGE	EMBK BALANCE (FILL)	FURNISHED EXCAVATION WASTE (+) SHRTGE (-)
	CU YD	CU YD	CU YD	CU YD
<b>LASALLE COUNTY</b>				
STA 810+00 - 841+40 EB MED	361	271	76	195 *
STA 841+40 - 885+00 EB MED	563	422	273	149 *
STA 885+00 - 937+90 EB MED	767	575	222	353 *
STA 937+90 - 990+89 EB MED	521	391	321	70 *
STA 990+89 - 1043+90 EB MED	545	409	1044	-635
STA 1043+90 - 1096+90 EB MED	516	387	1064	-677
STA 1096+90 - 1149+78.5 EB MED	642	482	498	-16
STA 810+00 - 841+40 WB MED			0	0
STA 841+40 - 885+00 WB MED			135	-135
STA 885+00 - 937+90 WB MED			301	-301
STA 937+90 - 990+89 WB MED			170	-170
STA 990+89 - 1043+90 WB MED			750	-750
STA 1043+90 - 1096+90 WB MED			683	-683
STA 1096+90 - 1149+78.5 WB MED			651	-651
<b>LASALLE CO. SUBTOTAL</b>	<b>3915</b>	<b>2936</b>	<b>6188</b>	<b>-4018</b>
<b>GRUNDY COUNTY</b>				
STA 1149+78.5 - 766+50 EB MED	533	400	301	99 *
STA 766+50 - 819+40 EB MED	693	520	149	371 *
STA 819+40 - 846+97 EB MED	342	257	129	128 *
STA 1149+78.5 - 766+50 WB MED			254	-254
STA 766+50 - 819+40 WB MED			152	-152
STA 819+40 - 846+97 WB MED			30	-30
<b>GRUNDY CO. SUBTOTAL</b>	<b>1568</b>	<b>1176</b>	<b>1015</b>	<b>-436</b>
<b>PROJECT TOTALS</b>	<b>5483</b>	<b>4112</b>	<b>7203</b>	<b>-4454</b>

STA 1155+51.21 BK = STA 724+16 AHEAD  
 \* - ALL WASTE AMOUNTS TO BE UTILIZED IN THE EB FORESLOPE FROM WHICH IT WAS GENERATED.  
 SHRINKAGE FACTOR = 25%  
 FURNISHED EXCAVATION = EMBANKMENT - (EARTH EX. X (1 - SF))

INLET AND PIPE PROTECTION		
LOCATION	STATION	INLET AND PIPE PROTECTION
		EACH
<b>LASALLE COUNTY</b>		
MEDIAN	831+79	1
MEDIAN	840+60	1
MEDIAN	848+00	1
MEDIAN	861+08	1
MEDIAN	867+70	1
MEDIAN	872+63	1
MEDIAN	883+19	1
LT & RT	884+40	2
LT	885+50	1
MEDIAN	893+00	1
MEDIAN	897+50	1
MEDIAN	914+80	1
MEDIAN	924+50	1
MEDIAN	935+68	1
MEDIAN	948+00	1
MEDIAN	952+00	1
MEDIAN	958+75	1
MEDIAN	968+75	1
MEDIAN	974+00	1
MEDIAN	982+61	1
LT & RT	989+85	2
MEDIAN	990+00	1
MEDIAN	996+00	1
MEDIAN	1002+12	1
MEDIAN	1018+00	1
MEDIAN	1031+00	1
LT & RT	1041+80	2
MEDIAN	1042+00	1
MEDIAN	1047+74	1
MEDIAN	1055+74	1
MEDIAN	1063+00	1
MEDIAN	1073+00	1
MEDIAN	1082+00	1
MEDIAN	1096+00	1
LT & RT	1096+20	2
MEDIAN	1109+74	1
MEDIAN	1121+00	1
MEDIAN	1142+73	1
LT & RT	1149+20	2
<b>LASALLE CO. SUBTOTAL</b>		<b>44</b>
<b>GRUNDY COUNTY</b>		
MEDIAN	1151+00	1
MEDIAN	734+68	1
MEDIAN	741+75	1
MEDIAN	751+90	1
MEDIAN	765+60	1
LT & RT	765+65	2
MEDIAN	767+00	1
LT & RT	767+00	2
MEDIAN	791+00	1
MEDIAN	803+00	1
MEDIAN	813+20	1
MEDIAN	822+25	1
MEDIAN	844+00	1
<b>GRUNDY CO SUBTOTAL</b>		<b>15</b>
<b>PROJECT TOTALS</b>		<b>59</b>