


SHOULDER REMOVAL; ±6" OF HMA OVER CRUSHED GRAVEL STONE TO BE MILLED & TRUCK AWAY.

PROP. EARTH EXCAVATION
PROP. HMA SHLD. 10"

PIPE UNDERDRAIN OUTLET
EXTENSION (SPECIAL)
AS NEEDED

EARTH
EXCAVATION



PROP. EARTH EXCAVATION

NOTES

- EXCAVATION FOR THE HMA SHOULDER WILL BE MEASURED AND PAID FOR AS "EARTH EXCAVATION". THIS EXCAVATED MATERIAL SHALL BE UTILIZED IN THE FORESLOPES OF THE MEDIAN AND SHAPED TO THE LINES AND GRADES SHOWN IN THE CROSS SECTIONS. BEFORE SEEDING, IT WILL BE NECESSARY TO DEEPLY DISK ALL THE DISTURBED AREAS ACCORDING TO 205.03.
- SEVERAL LOCATIONS MAY REQUIRE ADDITIONAL FILL TO PROVIDE A MINIMUM 1:4 FORESLOPE. THIS MATERIAL WILL BE PAID FOR AS "FURNISHED EXCAVATION".
- EXISTING PIPE UNDERDRAIN STRUCTURES MAY NEED TO BE ADJUSTED TO MATCH THE PROPOSED SLOPE, AND WILL BE PAID AS "PIPE UNDERDRAIN OUTLET EXTENSION (SPECIAL)".

NOT TO SCALE

| | | | | | | | | | | | | |
|--|--|------------|-----------|---|------------------------------|-----------------------|-----------|--------------------|---------|---------------------------|-----------------|--------------|
| FILE NAME = | USER NAME = corcoranlm | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | MEDIAN GRADING DETAIL | | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ca\pw\work\p\dot\corcoranlm\d0180581\d | 66A08-shd-details.DGN | DRAWN - | REVISED - | | 80 | (50-5,6 & 32-1,2)RS-3 | * | 76 | 39 | | | |
| | PLOT SCALE = 50,0000' / IN. | CHECKED - | REVISED - | | * LASALLE & GRUNDY | | | CONTRACT NO. 66A08 | | | | |
| | PLOT DATE = Mar 11, 2010 - 02:07:12 PM | DATE - | REVISED - | | SCALE: | SHEET NO. | OF SHEETS | STA. | TO STA. | ILLINOIS FED. AID PROJECT | | |