

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ONLY THOSE TREES DESIGNATED BY THE ENGINEER OR LISTED IN THE TREE REMOVAL SCHEDULE SHALL BE REMOVED. THE CONTRACTOR SHALL PROTECT ALL REMAINING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

MEMBERS OF JULIE KNOWN TO BE WITHIN THE LIMITS OF THE IMPROVEMENT ARE:

- COMMONWEALTH EDISON
- AT & T
- COMCAST
- NICOR GAS

NO EARTH/EMBANKMENT MATERIAL MAY BE REMOVED OFFSITE. THE EARTH SOIL MAY BE MOVED AS LONG AS IT STAYS ON SITE. IF CONSTRUCTION OPERATIONS REQUIRE THAT EARTH MATERIAL TO REMOVED OFFSITE THE DISTRICT 3 ENVIRONMENTAL UNIT SHALL BE CONTACTED AT 815-434-8569 PRIOR TO ANY EARTH REMOVAL OPERATIONS. ANY EARTH REMOVAL OPERATIONS AT THIS SITE, AS DIRECTED BY THE ENGINEER, WILL REQUIRE OBTAINING AN ENVIRONMENTAL FIRM TO MONITOR THE OFFSITE REMOVAL AT THE EXPENSE OF THE CONTRACTOR.

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | CONSTRUCTION CODE TYPE: | | URBAN 100% STATE |
|------------|--|-------------------------|------|---------------------|
| | | UNIT | Y004 | TOTAL QUANTITY |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | | 34 |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | | 24 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | | 1467 |
| 25000200 | SEEDING, CLASS 2 | ACRE | | 0.3 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | | 27 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | | 27 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | | 27 |
| 25100115 | MULCH, METHOD 2 | ACRE | | 0.3 |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | | 30 |
| 67100100 | MOBILIZATION | L SUM | | 1 |
| Z0007601 | BUILDING REMOVAL NO. 1 | L SUM | | 1 |
| Z0007602 | BUILDING REMOVAL NO. 2 | L SUM | | 1 |
| * Z0049901 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1 | L SUM | | 1 |
| * Z0049902 | REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2 | L SUM | | 1 |

* SPECIALTY ITEMS

TOPSOIL & SEEDING

| BUILDING NUMBER (PARCEL #) | TOPSOIL FURNISH AND PLACE 4" | SEEDING CLASS 2 | NITROGEN FERTILIZER NUTRIENT | PHOSPHORUS FERTILIZER NUTRIENT | POTASSIUM FERTILIZER NUTRIENT | MULCH METHOD 2 |
|-------------------------------|------------------------------|-----------------|------------------------------|--------------------------------|-------------------------------|----------------|
| | SQ YD | ACRE | TON | TON | TON | ACRE |
| 1 (3KC0043) | 403 | 0.08 | 7 | 7 | 7 | 0.08 |
| 2 (3KC0042DED) | 1064 | 0.22 | 20 | 20 | 20 | 0.22 |
| TOTALS | 1467 | 0.30 | 27 | 27 | 27 | 0.30 |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: David Brown
ACTING DISTRICT STUDIES & PLANS ENGINEER

DATE: January 28, 2010

EXAMINED BY: Robert K. Dwyer
DISTRICT CONSTRUCTION ENGINEER

James A. Huescher
DISTRICT MATERIALS ENGINEER
James A. Huescher
DISTRICT OPERATIONS ENGINEER