

MAINLINE SCHEDULE										
LOCATION MILE MARKERS		CENTERLINE REPAIR HMA SURF REM SPECIAL SQ YD	HOT-MIX ASPH. SURF. REM 2" SQ YD	HOT-MIX ASPH. SURF. REM 4" SQ YD	HOT-MIX ASPH. SURF. REM 5" SQ YD	POLY. HOT-MIX ASPH. SURF. MIX E N105 TON	POLY. HOT-MIX ASPH. BINDER IL-19.0 N105 TON	BIT MATL PR CT GAL	MIX FOR CR, JTS, & FLANGEWAYS TON	LEVEL BINDER (HM) TON
	LENGTH									
LASALLE COUNTY										
EASTBOUND DRIVING LANE										
74.34 TO 74.43	450			600		50	84	78.0	0.18	0.30
74.66 TO 75.56	500			667		56	93	86.7	0.20	0.33
75.25 (IL 251 ENT. RAMP)	40			53		4	7	6.9	0.02	0.03
76.24 TO 76.51	1350			1800		151	252	234.0	0.54	0.90
76.75 TO 76.98	1200			1600		134	224	208.0	0.48	0.80
77.85 TO 78.06	1050			1400		118	196	182.0	0.42	0.70
78.22 TO 78.3	400			533		45	75	69.3	0.16	0.27
78.45 TO 78.82	1850			2467		207	345	320.7	0.74	1.23
78.6 (I-39 INSIDE CIRCLE RAMP)	80			107		9	15	13.9	0.03	0.05
79.81 TO 80.15	1700			2267		190	317	294.7	0.68	1.13
82.15 TO 82.36	1050			1400		118	196	182.0	0.42	0.70
82.73 TO 82.76	150			200		17	28	26.0	0.06	0.10
90.3 TO 90.4	500		667			75		86.7	0.20	0.33
91.8 TO 91.9	500		667			75		86.7	0.20	0.33
93.1 TO 93.2	40		53			6		6.9	0.02	0.03
93.2 TO 93.8	3000	667				149		86.7	0.20	0.33
EASTBOUND PASSING LANE										
78.61 TO 79.32	20			27		2	4	3.5	0.01	0.01
79.32 TO 79.73	20			27		2	4	3.5	0.01	0.01
79.73 TO 87.15	20		27	27		2	4	3.5	0.01	0.01
87.15 TO 88.22	20		27			3		3.5	0.01	0.01
88.22 TO 93.2	20		27			3		3.5	0.01	0.01
93.2 TO 93.2	30		40			4		5.2	0.01	0.02
WESTBOUND DRIVING LANE										
95.6 TO 93.4	150				200	17	39	26.0	0.06	0.10
93.4 TO 93.25	500	111				25		14.4	0.03	0.06
93.25 TO 93.08	750		1000			112		130.0	0.30	0.50
93.08 TO 92.6	50		67			7		8.7	0.02	0.03
92.6 TO 92	3250	722				162		93.9	0.22	0.36
92 TO 91.1	500		667			75		86.7	0.20	0.33
91.1 TO 90	4000	889				199		115.6	0.27	0.44
90 TO 88.49	300	67				15		8.7	0.02	0.03
88.49 TO 80.15	550		733			82		95.3	0.22	0.37
80.15 TO 78.1	750			1000		84	140	180.0	0.30	0.50
78.1 TO 77.4	60			80		7	11	14.4	0.02	0.04
77.4 TO 76.2	2000	444				100		57.8	0.13	0.22
76.2 TO 75.44	2600	578				129		75.1	0.17	0.29
75.44 TO 75.2	1000	222				50		28.9	0.07	0.11
75.2 TO 75.25	250			333		28	47	60.0	0.10	0.17
75.25 (IL 251 EXIT RAMP)	60			80		7	11	14.4	0.02	0.04
74.85 TO 74.75	150			200		17	28	36.0	0.06	0.10
74.75 (IL 251 ENT. RAMP)	45			60		5	8	10.8	0.02	0.03
74.75 (IL 251 ENT. RAMP-EDGE LINE)	280	62				14		8.1	0.02	0.03
74.72 TO 74.25	100			133		11	19	24.0	0.04	0.07
74.25 TO 74.15	1750	389				87		50.6	0.12	0.19
WESTBOUND PASSING LANE										
93.9 TO 89	20				27	2	5	3.5	0.01	0.01
89 TO 87.15	60		80			9		10.4	0.02	0.04
87.15 TO 85.15	40		53			6		6.9	0.02	0.03
85.15 TO 83.28	20			27		2	4	4.8	0.01	0.01
83.28 TO 82.42	150			200		17	28	36.0	0.06	0.10
82.42 TO 79.15	20			27		2	4	4.8	0.01	0.01
79.15 TO 74.25	150			200		17	28	36.0	0.06	0.10
TOTAL	33545	4151	4080	15513	227	2709	2216	3233	7	12

LOOPS IN PAVEMENT IN AREA AROUND MM99.8-OMIT-DO NOT DISTURB-SEE DETAIL

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\p\WIDOT\BRABOYPC\d8179274\036615-ht-detail.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -					BQ	(50-2,3,4,5,6)-2	LASALLE	I	4
PLOT DATE = Jan 20, 2018 - 10:09:24 AM	DATE -	CHECKED -	REVISED -					CONTRACT NO. 66A15				
								SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	