

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 URBAN 100% STATE	1000 RURAL 100% STATE	URBAN Y025 CITY OF TREMONT 50% STATE 50% CITY	Y031-1F TRAFF SIG 100% STATE	Y031-1F TRAFF SIG 90% STATE 10% CITY
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	70	22	48			
40600300	AGGREGATE (PRIME COAT)	TON	414	132	282			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	538	1,470	3,911	⚠		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	654	283	371			
40600990	TEMPORARY RAMP	SQ YD	985	572	413			
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXD, N50	TON	3,743		3,743			
40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	8,128	2,940	5,188	⚠		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	74		74			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	51,496		51,496			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	87,035	44,112	42,923			
44003100	MEDIAN REMOVAL	SQ FT	9,308		9,308			
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1,379		1,379			
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1,789	1,680	109			
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1,185	544	641			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,690	321	3,369			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,412	1,048	364			
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	9,308		9,308			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3		3			
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	3		3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5			
67100100	MOBILIZATION	L SUM	1	0.2	0.8			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.2	0.8			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.2	0.8			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.8	⚠		

⚠ REVISED 4/13/10

*SPECIALTY ITEM

FILE NAME = 68460 Phase II.dgn	USER NAME = jacobamr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 693	SECTION 115RS-5, 118RS-7	COUNTY TAZEWELL	TOTAL SHEETS 36	SHEET NO. 4
PLOT SCALE = 100,0000' / IN.		DRAWN -		SHEET NO. 1 OF 3 SHEETS		CONTRACT NO. 68460				
PLOT DATE = 2/1/2010		CHECKED -		ILLINOIS FED. AID PROJECT						
		DATE -								
		REVISED -								