

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 URBAN 100% STATE	1000 RURAL 100% STATE	URBAN Y025 CITY OF TREMONT 50% STATE 50% CITY	Y031-1F TRAFF SIG 100% STATE	Y031-1F TRAFF SIG 90% STATE 10% CITY
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.2	0.8			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.3			0.7	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24,076	12,596	11,480			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	820	681	139			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109,163	16,488	92,675			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,751	2,363	388			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4,269	3,476	793			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,310	409	901			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	440	408	32			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,007	1,050	957			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	785	286	499			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	3		3			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3		3			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	785	286	499			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	926				926	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2,928	2,928				
* 89502105	REBUILD EXISTING SIGNAL HEAD, LED	EACH	8				8	
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1				1	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	15		15			
X0322729	MATERIAL TRANSFER DEVICE	TON	11,871	2,940	8,931			
* X0323336	^{SIGNAL} LED FACE RETROFIT, RED BALL	EACH	8					8
* X0323337	^{SIGNAL} LED FACE RETROFIT, GREEN BALL	EACH	8					8
* X0323418	^{SIGNAL} LED FACE RETROFIT, YELLOW BALL	EACH	8					8
* X0326101	BOND TRAFFIC SIGNAL STRUCTURE	EACH	17				17	

*SPECIALTY ITEM

⚠ REVISION
4-13-10