

URETHANE PAVEMENT MARKING SCHEDULE

LOCATION	LETTERS AND SYMBOLS	LINE 4"		LINE 6"	LINE 8"	LINE 12"		LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	
	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	TWO-WAY	ONE-WAY
	SQ FT	FT		FT	FT	FT		FT	EACH	
STA. 87+75.00 TO STA. 135+00.00	681.20	8,492	7,996	2,363	3,476	408.81		408.00		286
STA. 135+00.00 TO STA. 142+50.00		1,513	2,450	188						49
STA. 142+50.00 TO STA. 146+85.00		877	2,020				313.20			25
STA. 146+85.00 TO STA. 300+00.00	62.40	30,380	15,315						192	
STA. 300+00.00 TO STA. 304+98.00		1,261	1,568				95.30			19
STA. 304+98.00 TO STA. 312+49.00		1,474	751		172					5
STA. 312+49.00 TO STA. 315+12.00		516	1,294				74.90			
STA. 315+12.00 TO STA. 331+44.00		3,203	1,632						21	
STA. 331+44.00 TO STA. 339+80.00	76.50	1,641	3,024		302		195.80			38
STA. 339+80.00 TO STA. 340+15.00		69	35			95.90		32.00		
STA. 340+15.00 TO STA. 345+19.00		989	2,013		319		125.80			7
STA. 345+19.00 TO STA. 412+63.00		13,340	6,744						85	
STA. 412+63.00 TO STA. 435+00.00			567	200					57	
SUB-TOTAL	820.10	63,754	45,409	2,751	4,269	505	805	440.00	356	429
TOTAL	820	109,163		2,751	4,269	1,310		440	785	

NOTE: PRIOR TO PLACING CENTERLINE STRIPING, CONTACT THE DISTRICT BUREAU OF OPERATIONS FOR A "NO PASSING ZONE" EVALUATION

CHANGEABLE MESSAGE SIGN		
LOCATION	NO. SIGNS	CAL DA
PEKIN	1	28
TREMONT	1	28
TOTAL		56

TRAFFIC CONTROL AND PROTECTION						
LOCATION	STD. 701201	STD. 701306	STD. 701336	STD. 701406	STD. 701601	STD. 701701
	L SUM	L SUM	L SUM	L SUM	L SUM	L SUM
IL 9	1	1	1	1	1	1
TOTAL	1	1	1	1	1	1

▲ REVISIED SHEET 4-12-10

FILE NAME = 68460 Phase II.dgn	USER NAME = j.hohnsontv	DESIGNED -	REVISED -
		DRAWN -	REVISED --
		CHECKED -	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. RTE. 693	SECTION 115RS-5, 118RS-7	COUNTY TAZEWELL	TOTAL SHEETS 36	SHEET NO. 14
CONTRACT NO. 68460				