

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 URBAN 100% STATE	1000 RURAL 100% STATE	URBAN Y025 CITY OF TREMONT 50% STATE 50% CITY	Y031-1F TRAFF SIG 100% STATE	Y031-1F TRAFF SIG 90% STATE 10% CITY
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	70	22	48			
40600300	AGGREGATE (PRIME COAT)	TON	414	132	282			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	538	1,470	3,911	⚠		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	654	283	371			
40600990	TEMPORARY RAMP	SQ YD	985	572	413			
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIXD, N50	TON	3,743		3,743			
40603560	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	8,128	2,940	5,188	⚠		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	74		74			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	51,496		51,496			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	87,035	44,112	42,923			
44003100	MEDIAN REMOVAL	SQ FT	9,308		9,308			
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1,379		1,379			
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1,789	1,680	109			
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1,185	544	641			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,690	321	3,369			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,412	1,048	364			
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	9,308		9,308			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3		3			
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	3		3			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5			
67100100	MOBILIZATION	L SUM	1	0.2	0.8			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.2	0.8			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.2	0.8			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.8	⚠		

⚠ REVISED 4/13/10

*SPECIALTY ITEM

FILE NAME = 68460 Phase II.dgn	USER NAME = jacobamr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 693	SECTION 115RS-5, 118RS-7	COUNTY TAZEWELL	TOTAL SHEETS 36	SHEET NO. 4
PLOT SCALE = 100,0000' / IN.		DRAWN -		SHEET NO. 1 OF 3 SHEETS		CONTRACT NO. 68460				
PLOT DATE = 2/1/2010		CHECKED -		ILLINOIS FED. AID PROJECT						
		DATE -								
		REVISED -								

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 URBAN 100% STATE	1000 RURAL 100% STATE	URBAN Y025 CITY OF TREMONT 50% STATE 50% CITY	Y031-1F TRAFF SIG 100% STATE	Y031-1F TRAFF SIG 90% STATE 10% CITY
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.2	0.8			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.3			0.7	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24,076	12,596	11,480			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	820	681	139			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109,163	16,488	92,675			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,751	2,363	388			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4,269	3,476	793			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,310	409	901			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	440	408	32			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,007	1,050	957			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	785	286	499			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	3		3			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3		3			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	785	286	499			
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	926				926	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	2,928	2,928				
* 89502105	REBUILD EXISTING SIGNAL HEAD, LED	EACH	8				8	
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1				1	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	15		15			
X0322729	MATERIAL TRANSFER DEVICE	TON	11,871	2,940	8,931			
* X0323336	^{SIGNAL} LED FACE RETROFIT, RED BALL	EACH	8					8
* X0323337	^{SIGNAL} LED FACE RETROFIT, GREEN BALL	EACH	8					8
* X0323418	^{SIGNAL} LED FACE RETROFIT, YELLOW BALL	EACH	8					8
* X0326101	BOND TRAFFIC SIGNAL STRUCTURE	EACH	17				17	

*SPECIALTY ITEM

▲ REVISED
4-13-10

URETHANE PAVEMENT MARKING SCHEDULE

LOCATION	LETTERS AND SYMBOLS	LINE 4"		LINE 6"	LINE 8"	LINE 12"		LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	
	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE	TWO-WAY	ONE-WAY
	SQ FT	FT		FT	FT	FT		FT	EACH	
STA. 87+75.00 TO STA. 135+00.00	681.20	8,492	7,996	2,363	3,476	408.81		408.00		286
STA. 135+00.00 TO STA. 142+50.00		1,513	2,450	188						49
STA. 142+50.00 TO STA. 146+85.00		877	2,020				313.20			25
STA. 146+85.00 TO STA. 300+00.00	62.40	30,380	15,315						192	
STA. 300+00.00 TO STA. 304+98.00		1,261	1,568				95.30			19
STA. 304+98.00 TO STA. 312+49.00		1,474	751		172					5
STA. 312+49.00 TO STA. 315+12.00		516	1,294				74.90			
STA. 315+12.00 TO STA. 331+44.00		3,203	1,632						21	
STA. 331+44.00 TO STA. 339+80.00	76.50	1,641	3,024		302		195.80			38
STA. 339+80.00 TO STA. 340+15.00		69	35			95.90		32.00		
STA. 340+15.00 TO STA. 345+19.00		989	2,013		319		125.80			7
STA. 345+19.00 TO STA. 412+63.00		13,340	6,744						85	
STA. 412+63.00 TO STA. 435+00.00			567	200					57	
SUB-TOTAL	820.10	63,754	45,409	2,751	4,269	505	805	440.00	356	429
TOTAL	820	109,163		2,751	4,269	1,310		440	785	

NOTE: PRIOR TO PLACING CENTERLINE STRIPING, CONTACT THE DISTRICT BUREAU OF OPERATIONS FOR A "NO PASSING ZONE" EVALUATION

CHANGEABLE MESSAGE SIGN		
LOCATION	NO. SIGNS	CAL DA
PEKIN	1	28
TREMONT	1	28
TOTAL		56

TRAFFIC CONTROL AND PROTECTION						
LOCATION	STD. 701201	STD. 701306	STD. 701336	STD. 701406	STD. 701601	STD. 701701
	L SUM	L SUM	L SUM	L SUM	L SUM	L SUM
IL 9	1	1	1	1	1	1
TOTAL	1	1	1	1	1	1

▲ REVISIED SHEET 4-12-10

FILE NAME = 68460 Phase II.dgn	USER NAME = j. johnson	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. RTE. 693	SECTION 118RS-5, 118RS-7	COUNTY TAZEWELL	TOTAL SHEETS 36	SHEET NO. 14
CONTRACT NO. 68460				