

URETHANE PAVEMENT MARKING SCHEDULE											
LOCATION		LETTERS AND SYMBOLS	LINE 4"		LINE 6"	LINE 8"	LINE 12"		LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	
			WHITE	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	TWO-WAY	ONE-WAY
		SQ FT	FT		FT	FT	FT		FT	EACH	
STA. 87+75.00	TO STA. 135+00.00	681.20	8,492	7,996	2,363	3,476	408.81		408.00		286
STA. 135+00.00	TO STA. 142+50.00		1,513	2,450	188						49
STA. 142+50.00	TO STA. 146+85.00		877	2,020				313.20			25
STA. 146+85.00	TO STA. 300+00.00	62.40	30,380	15,315						192	
STA. 300+00.00	TO STA. 304+98.00		1,261	1,568				95.30			19
STA. 304+98.00	TO STA. 312+49.00		1,474	751		172					5
STA. 312+49.00	TO STA. 315+12.00		516	1,294				74.90			
STA. 315+12.00	TO STA. 331+44.00		3,203	1,632						21	
STA. 331+44.00	TO STA. 339+80.00	76.50	1,641	3,024		302		195.80			38
STA. 339+80.00	TO STA. 340+15.00		69	35			95.90		32.00		
STA. 340+15.00	TO STA. 345+19.00		989	2,013		319		125.80			7
STA. 345+19.00	TO STA. 412+63.00		13,340	6,744						85	
STA. 412+63.00	TO STA. 435+00.00			567	200					57	
SUB-TOTAL		820.10	63,754	45,409	2,751	4,269	505	805	440.00	356	429
TOTAL		820	109,163	45,409	2,751	4,269	1,310	440		785	

NOTE: PRIOR TO PLACING CENTERLINE STRIPING, CONTACT THE DISTRICT BUREAU OF OPERATIONS FOR A "NO PASSING ZONE" EVALUATION

CHANGEABLE MESSAGE SIGN		
LOCATION	NO. SIGNS	CAL DA
PEKIN	1	28
TREMONT	1	28
TOTAL		56

TRAFFIC CONTROL AND PROTECTION					
LOCATION	STD. 701201	STD. 701306	STD. 701336	STD. 701406	STD. 701601
	L SUM	L SUM	L SUM	L SUM	L SUM
IL 9	1	1	1	1	1
TOTAL	1	1	1	1	1